

(Periodical Surveys, when held, must be reported in detail and seriatim in the terms of the Rules and items remaining to complete the Surveys should be summarised. State clearly the cause of Repairs, if any, and, in detail, the nature and extent of Examinations and subsequent repairs. Repairs on account of Damage (the cause of which must be stated) should be separated from Repairs due to other causes; and besides being detailed in the body of the report, should be

1-39
B- 2031-39

Chalutier "CAP NORD" Ex ISLANDE G.T. 1034.

No. Book	Caractères	Dernier special survey No.3	- 1.39
05927		à Bordeaux L.M.C.	- 1.39
		C.L.	- 1.39

Résultat d'une visite officieuse sommaire :-

Le chalutier "CAP NORD", comme le "TERRE NEUVE" a été transformé en patrouilleur par les Chantiers de la Gironde à Bordeaux, sous le Contrôle des Constructions Navales, en Décembre 1939.

Le "CAP NORD" me parait avoir besoin d'une visite sérieuse, aux dires du chef mécanicien.

Les aiguillots du gouvernail ont un jeu de 8 m/m.

Les prises d'eau à la mer n'ont pas été visitées lors du dernier passage du navire en cale sèche (Décembre 1939).

Chaudière : Deux tubes tirants ont été tamponnés, pour fuites au renflement du dudgeonnage, coté boite à fumée. Un troisième tube fuit légèrement au même endroit.

Condenseur : Deux tubes sont tamponnés.

Arbre de butée : Les collets de l'arbre seraient fortement rayés et provoquent l'usure rapide de l'antifriction des colliers du palier.

La chaudière ayant les feux allumés, et le navire n'ayant pas été mis en cale sèche, la visite que j'ai faite n'a rien d'officiel et je n'ai d'ailleurs fait aucun rapport à ce sujet.

Casablanca, le 5 Mars 1940.

Alvarez



© 2021

Lloyd's Register
Foundation

W1045-0019

Transfer Ink
not to write

Special Damage or Repair Fee (if any).....£	:	:	19
(per Sec. 20)	:	:	
Travelling Expenses (if chargeable)	£	:	19

Received by me,

Surveyor to Lloyd's Register

d (if assigned) a
and now verifie

om?

ms :-

Copper, or Y.M.
(State if on F
When fitted, Month

Boats

Masts, Yards, &c.

Condition, how asc
(State if wea

Equipment letter

Anchors, No. of

Cables (State if n
,, length.....
(on boa

,, Rule length

Chain Locker

Hawsers & Warp

Standing and Run

Sails

l in the Register
main as classe