

Greenock Report nos. 9561 and ~~9566~~---

Dr. Reed
Dr. Reed (on road back)

22.12.87
18.1.88.

18. 188 Steel Screw Steamer

Scale $\frac{1}{2}$ inch = one foot.

Carrot 100 B. 1 stul non deck

Lappalaant Forecastle

Beams Bull $6\frac{1}{2} \times 6\frac{1}{2}$ Angles $2\frac{1}{2} \times 2\frac{1}{2} \times \frac{5}{8}$ on alternate frames
Stranger $24 \times \frac{1}{2}$ Firewall angles $3 \times 3 \times \frac{9}{16}$
Ties $9 \times \frac{1}{2}$ Sider plating $\frac{9}{16}$

Beams $6 \times 3 \times \frac{7}{8}$ on alternate frames

<u>Numbers for Scantling</u>	
Depth to keel	18' 8"
Half Breadth	16' 5"
Keel Depth	31' 8"
	<hr/>
List Number	66-7
Load on Deck	230
Second Number	13352.5
Addition of Equipment	1343.3
Equipment Number	16695.8

Proportions
12.32 Depths in Length
7. Beams to Length
poop. 134 feet long.
Forecastle 29 feet long.
Moulded Depth 17.112

Sheet stake doubled below stringer
at front of poop for 22 feet poop 1/2
with plate 22 x $\frac{9}{20}$

Equipment:

2	Bower Anchors	21	Col. & Hook
1	"	18	" " "
1	Stream	7 1/2	" " "
1	Redge	3 1/2	" " "
1	"	1 1/2	" " "
40	fathoms	1 1/2	" Mud chain Cable
75	"	1 1/2	" Stream chain
90	Fathoms	10	" Towline
90	"	8	" Bower
90	"	5 1/2	" Mapp.

Frank says $\frac{6}{7}$ thick. Balls & edges
all single rivetted as per par. 11 Sept 22
flange plate $\frac{7}{8}$ thick. ~~Double rivetted.~~
Sunk 10 Sept 22

Bottom shell plates BrC
Strakes lapped + double riveted
Bilge shul plating D.E. + L. Strakes
lapped + triple riveted
rivets in both 3" dia
c &c.

770li. Steel sizes in 20th

skill playing $\frac{11}{20}$ thick to be $\frac{1}{20}$ less in thickness
for double bottom

See other side
report.



Gr. 9566.

LLOYD'S REGISTER OF SHIPBUILDERS
RECEIVED
12 APR. 83.
LONDON

LLOYD'S REGISTER OF SHIPBUILDERS
RECEIVED
21 FEB. 83
LONDON

LLOYD'S REGISTER OF SHIPBUILDERS
RECEIVED
17 AUG. 83
LONDON

LLOYD'S REGISTER OF SHIPBUILDERS
RECEIVED
18 DEC. 83
LONDON

White

RETAIN



© 2020

Lloyd's Register
Foundation

W1049-0190