

COPY.

Lloyd's Register of Shipping.

71, Fenchurch Street, E.C.3.

22nd August, 1936.

Dear Sirs,

M.

With reference to your Mr. Ringsted's call at this Office to-day regarding a proposal to increase the width of the cargo hatches of your Nos. 69/70 from 1'-9" to 3'-9", I have to acquaint you that no compensation would be required to the upper deck plating in general where there are only two hatches fitted in the same transverse plane, but that immediately forward and aft of the bridge, where there are three hatches fitted in the same transverse plane, a doubling 14 mm. thick should be fitted to the centre strake in way of these hatches, or alternatively, one strake port and starboard abreast of these hatches should be increased by 5 mm.

I am, Dear Sirs,

Yours faithfully,

Secretary.

Messrs. Odense Staalskibsvaerft,

ODENSE.



© 2021

Lloyd's Register
Foundation

W1060142