

Messrs. Rykee & Co's No. 154.

Equipment Numeral:- 19525.


A letter has been received from the Rotterdam Surveyors stating that the cable makers at Schiedam have now proposed to make the cables for this vessel 45 m/m as they are unable to obtain material of 1-13/16 in.

The chain cable required by table 31 of the Rules is 240 fms. of 1-13/16 in. (1.81 in.), 397 cwt. 3 qr. 6 lbs. in weight (397.80 cwt.).

It is submitted that provided ^{an} additional 15 fathoms of 45 m/m (1.77 in.) chain cable be supplied making the total length and weight of the cable 255 fms. of 45 m/m (1.77 in.) = 403.28 cwt., the proposal is worthy of the favourable consideration of the Committee.

TUE. 13 JUN. 1916

C.T.
13.6.16



Approved *[Signature]*

Lr. 6/6/16
ansd. 13/6
2 plans c/p.



© 2020

Lloyd's Register Foundation

W1060-0108