

W1060-0156

AS  
s.s. "STANBALT" - Palmers S.B. & I. Co's No. 989.

----

Proposal to use this vessel for carrying cargoes of petroleum and alternatively asphalt within the circular tanks. (See ship endorsement).

With reference to the pumping arrangements it might be pointed out that in the event of the vessel carrying cargoes of petroleum in the circular tanks, the connection from the tanks and hold bilges to the ballast pump situated in the engine room space should be dispensed with. Provision would require to be made for the circular tanks and hold bilges to be drained either by the cargo pumps or by a special pump situated in the hold space containing the tanks. Further, the connection from the ballast main to the forward hold and fore peak water ballast tank would also require to be dispensed with and provision be made for draining these spaces by means of an additional pump situated forward of the bulkhead at frame No. 96 or, alternatively, by pipes led over the deck to the main engine room pumps.

A.T.G.

18.4.29.

© 2020

Lloyd's Register  
Foundation