

T.S.S. "CHELOHSIN".

Particulars taken from half model, also showing drillings and new plates.

All frames and plates counted from forward.

<u>Keel Plates</u>	No.	<u>Model</u>	<u>Port</u>	<u>Drillings.</u>	<u>Stbd.</u>
	1	18			
	2	19	19 ✓		18 ✓
	3	20			
	4	20	19		19
	5				
	6		20 ✓		20 ✓
	7	20			
	8	20			
	9	19	19 ✓		19 ✓
	11	18	New (furnaced Plate)		New
Practically vertical	12	18	New		New

All keel plates treble riveted butt straps (inner), width 37-1/2", 3/4" dia. rivets. Width of strap 15".

Seams 3/4" rivets. Double. 4-1/2" lap.

<u>"A" Strake</u>	No.			
	1	15	16 ✓	18 ✓
	2	12		
	3	13		
	4	14	14	13
	5	11		

<u>Strake</u> - at'd	No.	<u>Model.</u>	<u>Drillings</u>	
			<u>Port</u>	<u>Stbd.</u>
6	14		14 ✓	14 ✓
7	14			
8	14			
9	14		14 ✓	14 ✓
10	12			
11	12			
12	12	New	13 ✓	New 13 ✓

intercostal full length of engine room tank 50 to 62.

intercostal from 26 to 62.

these intercostals are on "A" Strake.

<u>Strake.</u>	No.			
1	18		18	18
2	18		18	18
3	13		11 ✓	11 ✓
4	14			
5	14			
6	14		13 ✓	13 ✓
7	14			
8	14			
9	14			
10	13		12 ✓	12 ✓
11	13			
12	13	New	13	New 13

intercostal on "B" Strake from 50 to 62

drilling tanks from 62 to 68.



© 2020

Lloyd's Register

File 6700079 2/6

	No.	<u>Model.</u>	<u>Drillings.</u>	
			<u>Port</u>	<u>Stbd.</u>
<u>C" Strake.</u>	1	18 with doubler 18		
	2	14		12
	3	14	14 ✓	18 ✓
	4	14		
	5	14		
	6	14	13 ✓	13 ✓
	7	14		
	8	14	12 ✓	12 ✓
	9	13	14 ✓	12 ✓
	10	14	12	
Boss Plates {	11	14	12	12
	12	14	12	12

lower stringer from Stem to 50, the after part being intercostal.

<u>D* Strake.</u>	No. 1	14	14	14
	(about Frame 11)			
	No. 2	14	12 ✓	14 ✓
	3	14	12	
	4	14	14	14
	5	14	14	12
	6	14	14 ✓	14 ✓
	7	13	12	14
	8	12	12	12
	9	11	10 ✓	9 ✓
	10	12	12	12



© 2020


Lloyd's Register
Foundation

W1067-0029 3/8

	<u>Model.</u>		<u>Drillings.</u>	
			<u>Port</u>	<u>Stbd.</u>
<u>"D" Strake (Cont'd)</u>				
Bilge keel 26 to 58.				
2 Boss plates Shown	14/40		12	12
2 " " above these also shown	14/40		12	12
<u>"E" Strake.</u>	No.1	18	18	18
	2	18	18	16
	3	13 ✓	13 New	12
	4	13	12	12
	5	13	13 New	New 13
	6	13	13 ✓ New	New 13 ✓
	7	13	12	
	8	13	12	14
	9	13	12	12
	10	12	12	12
	11	11 ✓	10 ✓	12 ✓
	12	11	10	12
	13	11	12	12

Lower deck on this strake Stem to After Peak (stringer E & B spaces).

<u>"F" Strake</u>	No. 1	11	14	14
	2	11	13 New	New 13
	3	12	13 New	New 13
	4	13	13 New	New 13
	5	13	13 New	New 13



© 2020

Lloyd's Register
Foundation

W1067-0029 4/6

	<u>Model.</u>	<u>Drillings.</u>	
		<u>Port</u>	<u>Stbd.</u>
<u>Strake (Cont'd)</u>	No.6	13	13
	7	13 ✓	11 ✓
	8	13	12
	9	13	12
	10	11	10
	11	11	10
	12	11 ✓	10 ✓
	13	10	10
<u>Strake Sheer.</u>	No.1	10	10
	2	11 ✓	11 ✓
	3	12	
	4	18	
	5	14	
	6	14	13 ✓
	7	14	13 ✓
	8	14	
	9	14	13
	10	13	12
	11	11	
	12	10	11 ✓
	13	13	

place practically horizontal.



© 2020

Lloyd's Register

Wlab7-00295/6

W. T. BULKHEADS.

Fore Peak on 7 to main deck.

Chain Locker on 10 to lower deck.

W.T. Bulkhead on 18 - has been changed to reinforced open deck.

W.T. Bulkhead on 31 to main deck.

W.T. Bulkhead on 39 boiler room to main deck.

Screen Bulkhead on 50.

After Engine Room Bulkhead on 62 to main deck.

After Peak on 79 to main deck.

1st. above main deck sheer - one plate renewed each side,
immediately forward of door in bulwark 10/40,
old plating 10/40.


Note:- Except for length of 14 feet the bulwark aft has
been plated in 10/40 to awning deck.

Rail on bulwark - 2-1/2" x 2" x 1/2" B. A.

Awning deck sheer strake - good - 10/40.

Plating above awning deck in way of accommodations now
renewed entirely - 8/40 - and ports substituted for
square windows. All house work entirely new.

Note:- All ports below main deck permanently closed
by riveted steel plates.



© 2020

Lloyd's Register
Foundation

W1067-0029 6/6