

SURVEYOR
OSLO

22.2.26

NIELSEN ALONSO PROPOSAL FIT ONE HORIZONTAL GIRDER IN CONJUNCTION
WITH FIFTEEN INCH VERTICAL CHANNEL STIFFENERS APPROVED PROVIDED
HORIZONTAL GIRDERS AS FOLLOWS ON TRANSVERSE BULKHEADS 165 AND
187 FIFTYFOUR BY POINT FIVENOUGHT WITH EIGHT INCH CHANNEL FACE
BAR ON MIDDLE LINE BULKHEAD 175 to 202 FIFTYONE BY FIVENOUGHT

WITH EIGHT INCH CHANNEL FACE BAR HAVING EIGHT BY SEVENTWO RIDER
PLATE MIDDLELINE BULKHEAD 165 TO 175 THIRTYFOUR BY FOURTWO WITH
EIGHT INCH CHANNEL ON FACE STOP HORIZONTAL GIRDERS FITTED
INTERCOSTALLY BETWEEN VERTICAL STIFFENERS AND CONNECTED TO
BULKHEAD PLATING BREADTH OF GIRDERS MEASURED FROM BULKHEAD



© 2019

Lloyd's Register
Foundation

W107-0160(1/2)

PLATING TO HEEL OF CHANNEL FACE BAR FITTED HEEL OUT FROM
BULKHEAD STOP BRACKETED ATTACHMENTS SUPPORTS AND CONNECTIONS
ON HORIZONTAL AND VERTICAL STIFFENERS IN ACCORDANCE REVISED
RULES FOR OIL TANKS RETURNING PLANS TONIGHT

COMMITTEE



© 2019

Lloyd's Register
Foundation

W107-0160C2/21