

s.s. "N.T.NIELSEN ALONSO" ex "POLCEVERA"

Plan showing the flensing deck above the awning deck and the alterations in way of the whale boilers submitted by the Oslo Surveyors.

It is submitted that provided doubling plates be fitted to the awning deck stringers and plating abreast the openings in way of the boilers, short intercostal girders be fitted amidships to maintain the continuity of strength, the whale boilers and winches be supported to the satisfaction of the Surveyor, and the arrangements otherwise be carried out as shown and amended on the plan and to the satisfaction of the Surveyors, the same will merit approval.


The Surveyors should forward a sketch of profile embodying the erections in the ship and all the new erections proposed to be arranged, in order that the equipment grade may be ascertained.

Ltr. 13/2. Ansd 18/2

2 Plans 1 Retained

BJF

18.2.26



© 2020

Lloyd's Register
Foundation

W107-0181