

FREEBOARD REPORT on the s.s. "ROSALIE"

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval.

SUBJECT TO:-

(1) The hatchway coamings, beams and fore and afters of Nos. 1 and 2 hatchways on the freeboard deck and the coamings, covers, tarpaulins and battening arrangements of the coaling hatchways on the raised quarter deck all being renewed or repaired ^e _k as required so as to be reasonably in accordance with the Convention requirements. The Surveyors should forward full particulars of these repairs.

(2) Efficient means of closing being provided for the air pipes, and the coaming of the 12" ventilator on the after deck being renewed as recommended by the Surveyor.

(3) Suitable provision being made for rigging lifelines which should be available for use in any part of the ship which might have to be used by the crew in the regular working of the ship.

(4) The locks of the doors in the forecastle bulkhead and exposed machinery casings being made efficient to the Surveyor's satisfaction.

The freeboards as computed under the Convention being in excess of the existing freeboards, the latter have been reassigned.

Ass. to Owners
& Sunderland 10.10.32.

[Handwritten signature]

[Handwritten initials]

10th October, 1932. H.S.N



© 2021

W1073-0244

Lloyd's Register Foundation