

COPY.

Lloyd's Register of Shipping.

71, Fenchurch Street, E.C.3.

ENCLOSURES.  
Air Mail.

10th February, 1938.

E.

Dear Sirs,

Hong Kong & Whampoa Dock Co's Yard No.782.  
-----

I duly received your letter of the 24th ultimo, enclosing plans (in quadruplicate) in connexion with the Electrical Installation proposed for the above vessel, and have to say it is noted that shunt wound generators are intended to be used and it is understood that these machines have already been ordered.

On examination of the plans, however, it is observed that electric winches, cranes and a windlass are to be installed, and as these services are liable to cause large and sudden vibrations in load on the generators, I have to state that shunt wound generators with normal field regulators are not suitable for this type of service and that series field windings are to be fitted to the two main generators.

Further, the plans of electrical installation will be approved, provided this installation be as shown and amended thereon, the remaining requirements of the Rules for Electrical Equipment (1937/38) be complied with and the installation be to your satisfaction.

W1075-0112 1/2



COPY.

2.

Hong Kong & Whampoa Dock Co's No.782.  
-----

Two sets of the plans are returned herewith,  
and one set is being forwarded to the Kobe Office for their  
records.

I am, Dear Sirs,

Yours faithfully,

Secretary.

The Surveyors,

HONG KONG.



© 2020

Lloyd's Register  
Foundation