


COPY.

*Hull*

# Lloyd's Register of Shipping.



Port NOTTINGHAM, 13th December, 1946.

Ruston & Hornsby Ltd., Engine No. 241306.

C. 4923.

MILFORD VISCOUNT - 54286.

700, 6VPHZ.

2019/T/13/450149.

339

This is to Certify that

E. D. Scott.

the undersigned Surveyor to this Society did at the request of

Messrs. Ruston & Hornsby Ltd., attend at their Works at Lincoln for the purpose of examining during construction and under test one six cylinder 4, S.O.S.A. Heavy Oil Engine No. 241306 manufactured by them to the order of Messrs. Cochrane & Sons Ltd. and intended for a trawler building by them. The engine is direct coupled to one compound wound, continuous rating electric generator, 372 Amps, 200 Volt No. 99305 having superimposed a belt driven exciter generator No. 149199, 4 K.W. 110 Volt all manufactured by Messrs. Laurence Scott & Electro Motors Ltd.

Particulars of the engine are as follows:-

Engine Number.....	241306.
Type.....	6VPHZ.
Number of Cylinders.....	6.
Diameter of Cylinders.....	5.5/8"
Stroke.....	8"
Maximum Pressure.....	300 lbs.
Brake Horse Power.....	130
Revolutions per minute.....	1000.
Span of Bearings.....	6.3/4"
Diameter of Journals.....	4.5/16"
Diameter of Crankpins.....	3.1/4"
Breadth of Webs.....	5.3/4"
Thickness of Webs.....	1.3/4"

The engine has been surveyed during construction in accordance with approved plans and the Regulations of this Society, materials and workmanship being good.

On completion, the engine was tested in the shops under working conditions with satisfactory results.

For purposes of identification the engine was stamped on the cylinder block thus:-

LLOYD'S TEST.  
50 lbs. T.D.S.  
21.6.46.  
Engine No. 241306.

*Scott*

Fee, £4.10s.0d.

SURVEYOR TO LLOYD'S REGISTER OF SHIPPING.

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:-

"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."