

THE CLARKSON THIMBLE TUBE BOILER CO. LTD.,
SHARMAN WORKS,
CAMBRIDGE ROAD,
HITCHIN.

Order 6544 /39/23.

Messrs. Abbott & Co., (Newark) Ltd,
Newark Boiler Works,
NEWARK-on-TRENT.

COPY

14th. August 1945.

CONTRACT NO. 3915.

ONE. Clarkson Patent Composite Boiler type "BATOC/190",
size 2'9" diameter shell, 4'2" dia. casing, x 8'9"
overall height. Working pressure 75 lbs/sq.inch,
hydraulic test pressure 150 lbs./square inch.

All generally as supplied to our order 2900/39/19
dated 19.1.40, but you to submit further drawings for
clients' approval.

1 Set Boiler Mountings, comprising:-

One 2" Main Steam Stop Valve; One D.S. Safety Valve;
Two combined Feed Check & Stop Valves; 3 Test Cocks;
1 set Water Gauges, 15" centres, complete with glass,
rings, and plate glass protector; One Blow-down Valve;
1 Salinometer Cock; 1 Pressure Gauge Cock on top crown
plate, with 10 ft. copper piping and hand control cock
with tee piece connection for Inspector's test gauge.
(N.B. Water gauge is to be fitted with Bewrance's
Bi-colour Illuminator).

ONE Spare Pressure Gauge.

ONE. Double Butterfly Valve to suit 7 bore piping, complete
with quadrant and lever. (extension on lever so that
quadrant can be operated by chains or extension levers)
Valve to be absolutely gas-tight, and not to rattle
when locked either open or shut to boiler.

ONE. Straight Length 7 bore piping 5'6" long x 3/16" thick,
with flanges drilled to suit Butterfly Valve.
21st. July 1946 certain.

Lloyds' Register of Shipping.

NOTE: Bore of piping to be advised
us by clients very shortly.

Nett monthly account.

Authorisation to follow.

Messrs. Ruston & Hornsby Ltd, ~~Sheffield~~ Ironworks, LINCOLN,
Job No.
marked: "Order B.41836/9 - Order 2047/T/13/450053".
Clarkson Boiler & Accessories.
paid.

Lloyd's Register
Foundation