

S.S. "GRAPHIC".

BUILT 1906.

CLASSED #100A1.

It is submitted that this plan of oil fuel suction pipes merits approval, provided the following conditions be complied with, viz :-

1. The Depth Gauges be found satisfactory when tested after fitting on board.
2. The air and overflow pipes of the oil fuel storage and overflow tanks be in accordance with the requirements of Section 49, Clause 10 of the Rules.
3. The connections between the oil fuel unit pumps and the gutterways in way of the storage tanks be dispensed with in order to comply with Section 49, Clause 13 of the Rules.
4. The remaining requirements of <sup>Section 49 of</sup> the Rules (1921-22) be complied with.

With reference to item 3 it is suggested that the suction from the gutterways should be connected to the bilge line or, alternatively, to a suitable hand pump.

It is concluded that the fuel tanks Nos. 1 and 2 (P & S) are to be used as settling tanks and that an oil fuel transfer pump will not be fitted.

It is also concluded that a plan of the oil fuel burning piping arrangements will be forwarded in due course.

Return plan.

*A.P.H.*  
*[Signature]*  
24/9/23.

*L 25/9/23*



© 2021

Lloyd's Register  
Foundation

W1079.0097