

Two messrs. ... 4/50 m/m.

25th Decr. '15.

M.S. "Bostonian".

Circuits on Main Switchboard.

<u>Group.</u>	<u>Cable.</u>	<u>Connected Load.</u>
Oil Fuel Pump.	7/18	7 amps.
Piston Cooling Pumps.	19/18	42 "
Forced Lubrication Pumps.	19/18	42 "
Circulating Pump.	19/15	86 "
Sanitary Pump.	19/15.	86 "
Refrigerating & Fresh Water Pump.	19/18	56 "
Ballast Pump.	19/15.	82 "
Bilge Pumps.	19/15.	79 "
Turning Gear Motors (Main Engine).	19/18	66 "
Workshop Motor.	19/18	26.5 "
Motor Room Lighting.	19/18	33.3 "
Spare.	-	-
Captain & Signals.	7/18	15.25 "
Officers & Passengers.	7/18	15.6 "
Engineers & Crew Lighting.	7/18	21.75 "
Cargo Lights.	19/15	48.5 "
Wireless.	7/18	20. "
Steering Gear.	19/15	77 "
Windlass & Winches Ford.	61/14 Ring Main	962 "
Winches aft.	37/15	" " 610 "

2 Main Dynamos. 3 pairs 61/.108 in parallel, each 682 amps. output.

1 Tuxham Driven Dynamo.



19/15. 68 amps. Output.

Lloyd Register Foundation

550181-0055