

ved by Chief Ship Surveyor

Received from Chief Ship Surveyor

SEL'S NAME Stl. S/S "EMPRESS of AUSTRALIA " Rpt. Ham. 15069
Gls. 42026 No.

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/32.)

re of Survey

Rule Dimensions : 589.8 x 75 x 46.2 Shelter dk.
Scantling Nos. 113.2 and 66755
Proportions: Length - 12.7 Depths to Shelter Dk.

This vessel was built in 1914 and classed with Germanischer Lloyd. Plans were examined and the vessel approved for the class 100 A1 with freeboard, provided the equipment be found to be in accordance with the Rules.

Reports have now been received from the Hamburg Surveyors giving particulars of scantlings, etc., which are generally in accordance with those approved.

The vessel has been examined in dry-dock, bottom cleaned and coated, the requirements of Sec. 48 of the Rules complied with, S.S. No. 2 carried out and minor repairs effected.

It is submitted the vessel appears worthy to be ~~in~~ classed:-

100 A1 with freeboard (See attached report 12)
2 Dks (Stl) and Shelter Dk (Stl-pt W.S.) 3rd Dk (Stl) in holds and cross bunker, 4th Dk (Stl) in forward and after holds.

Cell D.B. 467' 221ot FPT 183t APT 238t
FK 6 BH to Shelter Dk, 5 BH to Upper Dk. Lloyds A & C.P. Cem.
B. on Shelter Dk 348' F on Shelter Dk 113'. Promenade Dk 288'
Upper Promenade Dk. 280'

Date of Build 1914

5.22 Ham.

S.S. Ham. No. 2-22.

