

URGENT

LLOYD'S REGISTER

m.v. "JANKO" - No. 64185 in R.B.  
Carrying Petroleum in Bulk.  
-----

IT IS SUBMITTED the Kiel Surveyors be informed that the fitting of echo sounder transmitting and receiving oscillators in tankers other than in dry tanks in the engine room double bottom or forward of the forward cofferdam has been accepted only where it has been proved that correct functioning of the device cannot be achieved with the oscillators fitted in the recognised positions, each such case having been the subject of special consideration having regard to all the relevant circumstances.


There does not appear to be any special reason in the present instance for the installation of the sounder oscillators in the after cofferdam as the operational efficiency of the device would not appear to be materially affected by the moving of the oscillators a short distance aft of the position proposed to a dry tank in the engine room double bottom and it is accordingly desired that the Surveyors should discuss the matter with the Installers with a view to the adoption of the latter arrangement.

*Sa.*

5th September, 1950.

*Law*

letter 6/9



© 2020

Lloyd's Register  
Foundation

W1088-0131

that she be continued as classed in the Register Book with  
dry docking 12.50