

Lloyd's Register of Shipping.

71, Fenchurch Street, London, E.C. 3.

LLOYD'S REGISTER
LONDON.

7th October, 1919.

Dear Sir, RECD 8 OCT 1919

ANSR

"CRETESHADE".

The above vessel has been brought to Shoreham, and placed on the grid for the purpose of inspecting the bottom in accordance with the Society's request (see Secretary's letter dated 27th May, 1919 to Ministry of Shipping)

The inspection of the bottom shewed the following defects in the outer skin:-


A crack about three feet long on either side of centre keelson in Holdwell: water leaking through same from holdwell. At the forward end of after hold, starboard side, a narrow strip extending from bilge to centre keelson shews a number of voids and exposing reinforcement; also similar place on starboard side under boiler room.

Apart from these defects, the bottom appears to be in very good condition and free from voids.

Two small fractures appear in the outer skin at the port bow.

The above mentioned defects have now been made good and the bottom and sides twice coated with Wail's Dove's Solution.

I am, Dear Sir,
Yours faithfully,



Surveyor.

The Secretary,

LONDON.



© 2020

Lloyd's Register
Foundation

Referred to the Chief Ship Surveyor,

70 *ms*
OCT - 8 - 5

for the survey to make

Noted. J.T.M.

Cf.



© 2020

Lloyd's Register
Foundation