

COPY.

Lloyd's Register of Shipping,

71, Fenchurch Street, E.C.3.

15th October, 1937.

Dear Sirs,

E.

Messrs. J.L. Thompson & Sons' Yard No.591.
The N.E. Marine Eng. Co's Contract No.2920.

I duly received your letter of the 7th instant submitting for consideration proposed sizes of shafting in connexion with the above Contract.


In reply I have to inform you that, with Triple Expansion Steam Reciprocating Engines for Ocean Going Service, having diameter of cylinders 23", 38" and 65", stroke 42", working pressure 220 lb. per sq. inch, diameter of propeller 18'-0" and screw shaft with continuous liner, the following sizes of shafting will be approved, viz:-

Crank	13" dia.
Thrust	13" dia.
Intermediate ...	12 $\frac{1}{8}$ " dia.
Screw	14 $\frac{1}{8}$ " dia.

The particulars of shafting, as set forth in the list attached to your letter, will also be approved.

I am, Dear Sirs,
Yours faithfully,

The Surveyors,
SUNDERLAND.



Secretary.
Lloyd's Register
Foundation
W11-0115