

S.S.N° 257

SCALE  $\frac{1}{2}'' = 1 \text{ FOOT}$

LLOYDS. 100. A. I. CLASS

BREADTH	MLD	52.66
DEPTH		26.92
+ 5	FOR 8' 6" TWEEN DECKS.	50
TRANSVERSE	NUMBER	80.08
LENGTH	B P	399.6
LONGITUDINAL	NUMBER	31999
ERECTIONS CASINGS ETC.		2705
EQUIPMENT	NUMBER	34704
LENGTH + DEPTH	TO SHELTER DECK	11.28
	a	23.34

2 BOWER	ANCHORS	EACH	60 CWTs. STOCKLESS.
1	ANCHORS		50¢ " "
1	STREAM		10¢ " EX. STOCK.
1	KEDGE		7 " "
270	PATHOMS	2 3/8	STUD CHAIN CABLE
90	"	4 3/8	STEEL WIRE
120	"	4 3/4	TOWLINE
90	"	5	" HAWSER
90	"	5	" "
2 @ 90	"	2 1/2	" "

M. STRAKE  
76 FOR  $\frac{1}{2}L$  TO .44  
{ BUTTS QUADRUPLE RING FOR  $\frac{1}{2}L$   
TREBLE AT ENDS.

K. STRIKE (OUT).  
75 \* 66 FOR  $\frac{1}{2}$  L. TO 44.  
{ BUTTS QUADRUPLE RND FOR  $\frac{1}{2}$  L.  
{ TREBLE AT ENDS.

"U" STRIKE (IN) —  
66 x 66" FOR 1/2L TO .48  
44 IN PEAKS.

H STROKE (OUT).  
66 x 66 FOR EL. TO 48  
94 IN PEAKS.

"G" STROKE (IN).  
66 x 66" FOR 1/2 L TO .48"  
.44 IN PEAKS.

"E. STROKE (OUT)."  
66" X 66" FOR 1/2 L TO .48"  
.44 IN PEAKS.

E STRAKE (IN).  
66 X 62 TO 46  
BUTTS QUADRUPLE RIVETED FOR 1/2 L.  
TREBLE AT ENDS.

155.  
W. E.

6. 7. 20.



Messrs Northumbria shipbuilding  
Co Ltd,

S. S. No. 257

Midship section  
of vessel as built

S.S. "Monte Nevoso"

No. 73984.

RETAIN



© 2020

Lloyd's Register  
Foundation

W1101-0039