

Aux. Yacht "FLYING CLOUD".  
-----

Plans showing the jigger mast proposed to be utilised as an exhaust from the machinery have been forwarded by the Southampton Surveyors.

It is submitted the Southampton Surveyors be informed that the sizes of masts for yachts are not embodied in the yacht rules, but the Committee require that masts, where fitted, are in good condition.

The arrangement proposed appears to be satisfactory but the Surveyors should see that the support at the heel of the mast is fitted to their satisfaction and the arrangement for getting rid of the exhaust is satisfactory.

It is considered that man or hand holes should be arranged in the water jacket plating one above and the other below the upper deck to enable the mast to be examined periodically.

29/3 + 2/4/24  
used 4/4/24  
3 plans

B.C.C.

4.4.24.

J.M.B.

W.D.A.



© 2020

Lloyd's Register  
Foundation