

W1104-0125

Messrs. Cantiere Orlando's 4-masted Steel auxiliary yacht
"FLYING CLOUD"

Amended plan of arrangement of bulkheads forwarded by
Mr. Ormiston.

It is submitted the Genoa Surveyors be informed that the proposal to make a trunk passageway connecting the Owner's with the guests' accommodation in the tween decks and extending from frames 20 to 33 will be approved, provided the floor of the passage, as well as the sides, be made watertight. The proposal to fit a watertight door on the starboard side of the passage will also be approved.

The wing bulkheads at frames 20 and 33 should be watertight, and the watertight cabin deck flats should extend from frame 20 aft and from frame 64 to frame 33, as indicated on the plan.

It is considered that a watertight bulkhead fitted at frame 62 as shown on the plan ^{from the point of view of subdivision} will be advantageous.

The Genoa Surveyors might suggest to the Builders the advisability of forwarding any proposed amendments to previous approvals either in pencil or on a separate sketch, to obviate misunderstanding in case such proposals are not approved.

Spe

Ltr 4/9. Anod 15/9
1 Plan, Retained
p.c. Tri.

J.C.
14.9.25
BB

© 2020

Lloyd's Register
Foundation
1579