

Steel Yacht "FLYING CLOUD"

The above vessel is to be built under special survey at Leghorn and it is proposed to instal the propelling machinery ex the existing wood yacht "Flying Cloud".

The Owners and Builders desire to be advised whether the proposed arrangement of stern gear is suitable from the point of view that the shaft and propeller are of bronze and the stern tube of gunmetal and that these masses are in proximity to the steel hull.

IT IS SUBMITTED that the proposed arrangement of stern gear merits approval, provided the steel shell plating forming the bossing at the after end of the stern tube, and, also the after sides of the cast steel arms of the "A" brackets in way of the propeller blades, be protected by zinc plates, in metallic contact with the steel structure, to the Surveyors' satisfaction.

Return plan.

S.F.D.
30.12.25
Cms



© 2020

L.R.S.

Lloyd's Register
Foundation
W1104-0217

34/12/25