

Messrs Fratelli ORLANDO - Leghorn

Yacht "FLYING CLOUD"

Letter from the Builders proposing to fit 80 m/m. and 110 m/m. solid pillars in lieu of 110 x 10 m/m and 170 x 10 m/m pillars in the Tween Decks and Holds respectively.

It is submitted the Builders be informed that their proposal to fit 80 m/m. and 110 m/m solid pillars in lieu of 110 x 10 m/m. and 170 x 10 m/m. pillars in the Tween Decks and Holds respectively is in order but the diameter of the solid pillars in the Peep and Fore castle should be 75 m/m. diameter. - Also that ^{all} these Pillars should have flat palms with 4- 22 m/m rivets head and heel.

Genea 16th December 1925.

J.S.O.

h.g.



© 2020

Lloyd's Register
Foundation
W1104 6224