

H U L L .

24th April 1919.

J. G. MACKILLOP,

the Ministry of Shipping survey the Main boilers of the Steel Screw Steamer "POLYOLIA" 1831 tons (gross) register while the vessel was lying in the Albert and Alexandra docks, Hull, on the 13th March 1919 and subsequent dates.

On examination of the boilers found all in good order except the following defects, which were repaired as follows viz:-

Eight stays on starboard combustion chamber, and six on Port Chamber of Port boiler, which were badly wasted, now renewed. Main feed pipe in Starboard boiler, which was badly wasted now renewed. The spigot plates of both bottom manhole doors are somewhat wasted, these were not repaired, and this latter defect is not serious.

The safety valves and mountings of both boilers were overhauled and put in order.

Safety valves of both main boilers were adjusted under steam when the above mentioned repairs were found tight and satisfactory.

Fee. £4 : 4 :

J. G. Mackillop
SURVEYOR FOR LLOYD'S REGISTER OF SHIPPING.



© 2020

Lloyd's Register
Foundation

W1108-0028