

Boilers No 884 & 885  
Machinefabriek Delft Haven.  
List of Thicknesses of Material etc.

	Millimeter	Inch.
Shell plates	19	3/4
Butt straps	19	3/4
Over rivet holes	27	1 1/16
Pitch of rivets	130	5 1/8
Compensating ring round manhole	100 x 20	<del>1 1/8 x 3/4</del> 3 15/16 x 25/32
Diam of furnaces	800	31 1/2
Thickness of D.	16 <del>14</del>	5/8 <del>7/8</del> 22
Comb: chamber sides, back, top & bottom	16	5/8
Pitch of stays at sides	180 x 180	7 1/16
" " at top	175 x 200	6 7/8 x 7 7/8
" " at back	180	7 1/16
Ext Diam of screeners	35	1 3/8
Forward end plate	22	27/32
Back end plate	20	25/32
Pitch of steam space stays	380	15
D.	360	14 3/16
Diam of <del>longitudinal</del> longitudinal stays	63	2 1/2
Greatest pitch of stays to back end plate	280	11
Diam of plain tubes	83	3 1/4
" stay tubes	76	3
Pitch of tubes	106	4 3/16
Back tube plate	22	27/32
Pitch across wide water space.	370	14 9/16
Depth of girders	200	7 7/8
Thickness of d.	30	1 3/16
Level per inch	560	22
Distance apart	200	7 7/8
Pitch of stays in girders	175	6 7/8

W 1108 - 0176



© 2020

Lloyd's Register  
Foundation