

For the information of Surveyors and the Committee only.

Received at

Office

19

Lloyd's Register of Shipping.

(Report on Vessel No. 7395 Port Trieste)

F.28

SHIP FORGINGS OR CASTINGS

I have to report that the undermentioned ~~Iron or~~ Steel Forgings ~~or~~ castings, manufactured by Messrs SOCIETA' ITALIANA ERNESTO BRED A Sesto San Giovanni for the Vessel No. 20, being built by Messrs Cantiere Navale of Mestre have been inspected by me as set forth below and found to be, so far as can be seen, sound and free from defects. -

Forgings or Castings

Lloyd's

No. 2

M. - 19.2.26

GENOA, 26th February, 1926

	XXXXXXXXXX 1 RUDDER POST	3 RUDDER XXXXXXXXXX ARMS	XXXXX 1 RUDDER PINTLES
	S.M. ingot steel	S.M. ingot steel	S.M. ingot steel
	Forged & annealed	Forged & annealed	Forged & annealed
	m/m. 190x125	m/m. 140x85	Ø 85
on Inspection	Rough forged & finished	Rough forged & finished	Rough forged
Inspected	15 & 19/2/26 . -	15 & 19/2/26 . -	15 & 19/2/26 . -
STINGS.			
Standard Test	2 2	3	4
Pieces.	(75 x 20 m/m.)	(75 x 20 m/m.)	(75 x 20 m/m.)
Test—			
square mm	47.0	47.3	47.0
/m/m.	34	38	30
per cent.			
ling Test—			
fore fracture	180°; good	180°, good	180°, good
from ground ...			
ing Test—			
according to Rules (
und satisfactory ...)			

SKETCHES OF FRAMES SHOWING POSITION AND DESCRIPTION OF WELDS OF FORGINGS.

and expenses

if any chargeable) Lit. 515.00 :

to be paid at Genoa . -

iron, state whether scrap or puddled iron. If of Steel, state whether made on the Open Hearth process.

te if annealed. Yes . -

© 2020

Lloyd's Register
Foundation