

342-0 B.R. x 49-1 EXTREME x 25-4 MOULDED

SCALE $\frac{1}{8} = 1$ FOOT.

SECTION OF SIDE COAMINGS
OF 4 LARGE HATCHWAYS 24'-6" x 18'-0"

4- '50 SIDE CORMINGS. ✓
END CORMINGS = '40.

POOP FRONT BULKHEAD '38 ✓
'42 COAMING. ✓
52" x 32" x '34 ANG. STIFFERS. 2-6 APAR

6x6x50 AT SIDES
 40 AT ENDS.
 3x3x40 LUGS
 6x3x44 GIRDER BAR. 8" FLANGE.

B.R. BEAMS 8 x 3 x .50
KNEES 124 x .50
BULB AND BEAMS 6 1/2 x 3 x .40
2 R. SIZE.
KNEES 19 x .4
8/16 PL

BRIDGE FRONT BULKHEAD '38 ✓
'42 COMING. ✓
4 1/2 x 3 1/2 x 60 S.R. STIFFERS. 2-6 APR.
BRACKETED TOP & BOTTOM.

4 MAIN HATCHWAYS $24'6" \times 18'0"$ ✓
4 WEBS IN EACH ABOUT $4'11"$ APART $21'34"$ TO $16'34"$ ✓
 $4 \times 3' \times 40"$ ANGLES, ON UPPER & LOWER EDGES. ✓

ALTERNATE $10 \times 3\frac{1}{2} \times 54$ BULB ANGLE FRAMES TO BRIDGE DECK
INTERMEDIATE STIFFENERS IN BRIDGE $3\frac{1}{2} \times 3\frac{1}{2} \times 34$ ANGLE

BULKHEADS NO. 67 & 89.
PUTTING SHEATHING ALL '32, FRAME & T.T. BAR 5" x 46"
DICK BAR 5 1/2" x 3 1/2" x 34". 9 x 3 x 50 B.M. STIFFERS 2-6 APART. x 2-6"
BRACKETS TO SHELL AS SHOWN 2-0 x 2-0 x 42. BULKHEAD LINERS FITTED.

28.7.11.

BULKHEAD N. 131
 PLATING 34" x 40" ALL 32. FRAME & T.T. BAR 5" x 5" x 48
 UK. BAR 3 1/2" x 3 1/2" x 34. 11 1/2" x 52. B.A. STIFFEN. 2-6 APART. 2" x 6"
 BRACKETS TO SHELL AS SHOWN 2'0" x 2'0" x 42
 BULKHEAD LINERS FITTED.

BULKHEAD NO 159,
PLATING 36 TO 30, FRAME 3' x 5' x 42, OK BAR 4' x 4' x 36,
8 1/2' x 3' x 46" B.A. STIFFERS 2' 0" APART,
STIFFENED HORIZONTALLY BY SEAM BOX BEAM AS SHOWN.
END ABOVE W.T. FLAT STIFFENED BY 3 VERTICAL WEBS
& 8 1/2' x 3' x 36 VERTICAL STIFFERS. 2' 0" APART, AND
HORIZONTAL B.A. STIFFENER AS SHOWN. V

© 2021
SHEWN.
Lloyd's Register
Foundation

1112-0173

J L Thompson & Sons

No 490

Amended Profile.

"SS" SHAKESPEAR Sd Rpt No 25906

Ld Rpt 24651

25173



© 2021

Lloyd's Register
Foundation

W1112-0173