

"REGISTER, GLASGOW."

TELEPHONE: CENTRAL 6490 (4 LINES).

COPY

Lloyd's Register of Shipping,

342, Argyle Street, Glasgow.

20th January, 1922.

Dear Sir,

S.S. "GARTLAND" ex "IZMIR".

With reference to the classification of the Society's Register Book of the above vessel, I have to inform you that provided the requirements of Section 48 of the Rules for vessels not built under survey be complied with; brackets 36" deep be fitted connecting all watertight bulkhead stiffeners to the deck; the fore peak bulkhead be additionally stiffened as arranged on the ship; additional pillars be fitted in the bridge as arranged; doublings be fitted on the strake above the sheerstrake at the ends of the bridge; and a web 24" deep with brackets to the side stringers be fitted on the fifth or sixth frame from the collision bulkhead, the vessel will be eligible to be classed 100A-.

In order that the question of the figure "1" may be dealt with, I shall be glad if you will kindly forward the list of the equipment on board the vessel for consideration, together with the certificates of test.

I am, Dear Sir,
Yours faithfully,

Local Secretary.

W. McMeek, Esq.,
GLASGOW.

W1121-0233