

for Mr. Ward, Wokingham

"ADAMS BECK"

Burntisland S.B. Co's Yard No. 235

Rule Dimensions:- 312' x 44.25' x 22.08' to upper deck
27.08' to R.Q. deck

Class:- 100A1

On the earlier plans submitted a deep tank, 9' in length, was fitted amidships, and as the two bulkheads were considered in terms of the Rules as one bulkhead only, it was required that the notation "Intermediate bulkhead dispensed with; 4 B.H." be made in the Register Book.

Subsequently (6th June, 1940) an amended plan was submitted in which the deep tank amidships was omitted and a watertight bulkhead arranged between Nos. 1 and 2 holds, thus providing five watertight bulkheads as required by the Rules. It is assumed that this amended plan was worked to.

The equipment was approved in accordance with letter "t" of Table 53 of the Rules, excepting that a reduced length of cable (210 fathoms) was supplied and the third bower anchor omitted, with the Owners' consent, under the usual undertaking.

There are no further points in the correspondence affecting First Entry.

8th July, 1941.



© 2021

Lloyd's Register

WH23-0004

The Surveyors should be informed the overall length including the gun platform is 350.3 as per the plan of the vessel "ADAMS BECK" but they should state if this is so.

DOUBLE BOTTOM.

Solid Floors, thickness and spacing 34 EVERY

Spacing.....