

No. in Reg. Book. 70672 on the ~~Wood, Iron or Steel~~ *S.S. Belgravian* Date, First Survey 5.5.41 Last Survey 15.5.41 (No. of Visits) YEAR. 1931
TONNAGE: Built at *N. Harlepool* By whom *W. Gray & Co. Ltd.* When 1931
GROSS *3156* Owners *Ellerman & Lines Ltd.* General Address

Date 5th. May, 1941.

No. of Items.....

SPECIFICATION of REPAIRS s.s.

"BELGRAVIAN"

A.S. 187-5,000-5/40 (2680)-EW

Gunnery's Accommodation

New room to build in No.5 Tween Deck Port side, after corner, approx. sizes of room 19'0" long inside x 12'0" mean width; leave alleyway at Port side of hatch 2'0" wide.

Two 8" cowl ventilators to supply and fit. **One 6 1/2"*

16" Vent inside of space to trunk above over heading between beams through bulkhead into tween decks.

3 Steam heaters to supply and fit.

Wash place to be arranged at Port side of Tonnage space.

Two Dwarf Wash stands to supply and fit.

New iron companion to supply and fit over tonnage opening, also tonnage opening to plate up in place of same.

Entrance ladder leading from same to supply and fit.

Four Port lights with deadlights to supply and fit; three in room and one in washplace.

Electric light, also fans to supply and fit.

Wind scopp to fit to all Ports.

Ports, Ventilators and door to be fitted with Mosquito wire. Deck seams to be levelled up and covered with line.

Sailors W.C. aft starboard side marked Gunners.

