

REPORT ON ELECTRICAL EQUIPMENT.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

JAN 21 1939

Date of writing Report 12-1-39 When handed in at Local Office 20-1-39 Port of Glasgow.

No. in Survey held at Glasgow.

Date, First Survey 15:8:38 Last Survey 12-1-1939

(Number of Visits 10)

87272 on the M.V. "BRITISH TRUST"

Tons { Gross 8466
Net 4913

Built at Glasgow.

By whom built Harland & Wolff Ltd

Yard No. 10119

When built 1939

Owners British Tankers Co. Ltd

Port belonging to London

Electric Light Installation fitted by Harland & Wolff Ltd

Contract No. 10119 When fitted 1939

Is the Vessel fitted for carrying Petroleum in bulk Yes

System of Distribution

Two Wires.

Pressure of supply for Lighting 110

volts, Heating —

volts, Power 40

volts.

Direct or Alternating Current, Lighting Direct

Power Direct

If alternating current system, state frequency of periods per second —

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off Yes

Generators, do they comply with the requirements regarding temperature rise Yes, are they compound wound Yes

are they over compounded 5 per cent. Yes, if not compound wound state distance between each generator —

Where more than one generator is fitted are they arranged to run in parallel Yes

is an adjustable regulating resistance fitted in

series with each shunt field Yes

Have certificates of test results for machines under 100 kw. been submitted and

approved Yes

Have machines over 100 kw. been inspected by the Surveyors during manufacture and testing —

Are all terminals accessible, clearly marked, and furnished with sockets Yes

are they so spaced or shielded that they cannot be accidentally earthed,

short circuited, or touched Yes

Are the lubricating arrangements of the generators as per Rule Yes

Position of Generators

In main engine room.

is the ventilation

in way of the generators satisfactory Yes

are they clear of all inflammable material Yes

if situated near unprotected

woodwork or other combustible material, state distance of same horizontally from or vertically above the generators —

and —

are the generators protected from mechanical injury and damage from water, steam or oil Yes

Yes

are their axes of rotation fore and aft Yes

Yes

Earthing, are the bedplates and frames of the generating plant efficiently earthed Yes

Yes

are the prime movers and their respective generators

in metallic contact Yes

Main Switch Boards, where placed In engine room

If the generators and main switchboard are not placed in the same compartment, is each generator provided with

a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard —

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes Yes

are they protected from mechanical

injury and damage from water, steam or oil Yes

if situated near unprotected woodwork or other combustible material, state distance of same

horizontally from or vertically above the switchboards —

and —, are they constructed wholly of durable, non-ignitable non-absorbent

materials Yes

is all insulation of high dielectric strength and of permanently high insulation resistance Yes

is it of an approved type Yes

if semi-insulating material is used, are all conducting parts insulated from the slab with mica or micaite or other

non-hygroscopic insulating material, and the slab similarly insulated from its framework Yes

Yes

is the non-hygroscopic insulating material of an approved

type Yes

and is the frame effectively earthed Yes

Are the fittings as per Rule regarding:— spacing or shielding of live parts

Yes

accessibility of all parts Yes

absence of fuses on back of board Yes

Yes

temperature rise of

omnibus bars Yes

Yes

individual fuses to voltmeter, pilot or earth lamp Yes

Yes

are moving parts of switches alive in the

"off" position No

No

are all screws and nuts securing connections effectively locked Yes

Yes

are any fuses fitted on the live side of

switches No

No

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches

D.P. circuit breakers with interlocked equalizers fitted with 1/2" 1/2" trips for each generator, DP circuit fuses for each outgoing circuit.

Are turbine driven generators fitted with emergency trip switch as per rule —

Are cupboards or compartments containing switchboards composed of

fire-resisting material or lined with approved material —

Instruments on main switchboard 12

ammeters 3

voltmeters — synchronising device for paralleling purposes. For compound machines is the ammeter connected on the opposite pole to equaliser connection

Yes

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system

Card Lamps.

Switches, Circuit Breakers and Fusible Cut-outs.


do these comply with the requirements of the Rules Yes

Yes

are the fusible cutouts of an approved type Yes

Yes

have the reversed



current protection devices been tested under working conditions. *Yes* Joint Boxes, Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule. *Yes*

Cables: Single, twin, concentric, or multicore. *Single* are the cables insulated and protected as per Tables IV, V, X or XI of the Rules. *Yes*

If the cables are insulated otherwise than as per Rule, are they of an approved type. *Yes* Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load. *5.7 Volts* Cable Sockets, are the ends of all cables having a sectional area of 0.04 square inch and above provided with soldering sockets. *Yes*

Paper Insulated and Varnished Cambric Insulated Cables, If conductors are paper or varnished cambric insulated, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound. *Yes* or waterproof insulating tape. *Yes* Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage. *Yes* Are cables in machinery spaces, galleys, lavatories, bathrooms and lavatories lead covered or run in conduit. *Yes*

Support and Protection of Cables, state how the cables are supported and protected. *Main L.C.A.B. run on fore & aft gangway in library, nearly across L.C.A.B. clippel. Accommodation L.C. clippel.*

If cables are run in wood casings, are the casings and caps secured by screws. *Yes* are the cap screws of brass. *Yes* are the cables run in separate grooves. *Yes* If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII. *Yes*

Refrigerated Chambers, are the cables and fittings in accordance with the special requirements. *None*

Joints in Cables, state if any, and how made, insulated, and protected. *None*

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands. *Yes* Bushes in Beams and Non-watertight Partitions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed. *Yes* state the material of which the bushes are made. *Lead*

Earthing Connections, state what earthing connections are fitted and their respective sectional areas. *Metallie sheathing and armoring of cables efficiently bonded & earthed.* are their connections made as per Rule. *Yes*

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule. *Yes* Emergency Supply, state position and method of control of the emergency supply and how the generator is driven. *Yes*

Navigation Lamps, are these separately wired. *Yes* controlled by separate switch and separate fuses. *Yes* are the fuses double pole. *Yes* are the switches and fuses grouped in a position accessible only to the officers on watch. *Yes* has each navigation lamp an automatic indicator as per Rule. *Yes* Secondary Batteries, are they constructed and fitted as per Rule. *Yes*

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight. *Yes* are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected. *in special* are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected. *Top of pump rooms in special gastight fittings in gastight tubing outside of spaces.* where are the controlling switches situated. *in accommodation headships* are all fittings suitably ventilated. *Yes* are all switches and lampholders constructed wholly of non-ignitable, non-absorbent materials. *Yes*

Heating and Cooking Appliances, are they constructed and fitted as per Rule. *Yes* are air heaters constructed and fitted as per Rule. *Yes*

Searchlight Lamps, No. of *one* whether fixed or portable. *portable* are their fittings as per Rule. *Yes*

Are Lamps, other than searchlight lamps, No. of *one* are their live parts insulated from the frame or case. *Yes* are their fittings as per Rule. *Yes*

Motors, are their working parts readily accessible. *Yes* are the coils self-contained and readily removable for replacement. *Yes* are the brushes, brush holders, terminals and lubricating arrangements as per Rule. *Yes* are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material. *Yes* are they protected from mechanical injury and damage from water, steam or oil. *Yes* are their axes of rotation fore and aft. *blue possible* if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type. *Yes* if not of this type, state distance of the combustible material horizontally or vertically above the motors. *and*

have machines of over 100 BHP been inspected by the Surveyors during manufacture and testing. *Yes* Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule. *Yes* Lightning Conductors, where lightning conductors are required, are these fitted as per Rule. *Yes* Ships carrying Oil having a Flash Point less than 150 F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings. *Yes* are all fuses of the filled cartridge type. *Yes* are they of an approved type. *Yes*

If portable lamps for use in dangerous spaces are supplied, are they of a self-contained, battery-fed type approved by the Home Office. *Yes*

Spare Gear, if the vessel is for open sea service have spares been supplied as per Rule. *Yes*

PARTICULARS OF GENERATING PLANT.									
DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.		
		Kilowatts.	Volts.	Amps.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.	
MAIN ...	1	30	110	273	550	Steam Engine			
AUXILIARY ...	1	30	110	273	600	Oil Engine	Diesel Oil	Above 150° F.	
EMERGENCY ...									
AUXILIARY ...	1	8	110	73	750	Steam Engine			
ROTARY TRANSFORMER									

GENERATOR, LIGHTING AND HEATING CONDUCTORS.									
DESCRIPTION.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT. AMPERES.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
	No. per Pole.	Total Nominal Area per Pole Sq. Ins.	No.	Diameter.	Circuit.	Rule.			
MAIN GENERATORS...	1	4	61	0.93	273	288	70	Rubber	L.C.A.B.
EQUALISER CONNECTIONS	1	15	37	0.72	-	152	35	"	"
AUXILIARY GENERATOR...	1	06	19	0.64	73	83	45	"	"
EMERGENCY GENERATOR									
ROTARY TRANSFORMER MOTOR GENERATOR...									
ENGINE ROOM DB...	1	0225	7	0.64	31.3	46	80	"	"
BOILER ROOM DB...									
AUXILIARY SWITCHBOARDS									
ACCOMMODATION ...									
MOSBY 1000 Ltg. S.B. No. 1	1	06	19	0.64	40	83	600	"	"
AFT DB. S. 5A. 5B.	1	0145	7	0.52	25	37	280	"	"
NAVIGATION DB No. 1.	1	0225	7	0.64	15	46	700	"	"
WIRELESS ...	1	0145	7	0.52	20	37	700	"	"
SEARCHLIGHT ...	1	04	19	0.52	45	64	1300	"	"
MASTHEAD LIGHT ...	1	002	3	0.29	36	7.8	450	"	L.C.B. in library
SIDE LIGHTS ...	1	002	3	0.29	36	7.8	50	"	L.C.B.
COMPASS LIGHTS ...	1	002	3	0.29	18	7.8	30	"	"
POOP LIGHTS ...									
CARGO LIGHTS ...									
ARC LAMPS ...									
HEATERS ...									

MOTOR CONDUCTORS.										
DESCRIPTION.	No. of Motors.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT. AMPERES.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
		No. Per Pole.	Total Nominal Area per Pole Sq. Ins.	No.	Diameter.	In Circuit.	Rule.			
BALLAST PUMP ...										
MAIN BILGE LINE PUMPS ...										
GENERAL SERVICE PUMP ...										
EMERGENCY BILGE PUMP ...										
SANITARY PUMP ...										
CIRC. SEA WATER PUMPS ...										
CIRC. FRESH WATER PUMPS...										
AIR COMPRESSOR ...										
FRESH WATER PUMP ...										
ENGINE TURNING GEAR...	1	1	06	19	0.64	80	83	150	Rubber	L.C.A.B.
ENGINE REVERSING GEAR ...										
LUBRICATING OIL PUMPS ...										
OIL FUEL TRANSFER PUMP...										
WINDLASS ...										
WINCHES, FORWARD ...										
WINCHES, AFT ...										
STEERING GEAR—										
(a) MOTOR GENERATOR...										
(b) MAIN MOTOR ...										
WORKSHOP MOTOR ...	1	1	01	7	0.44	26.5	31	130	"	"
VENTILATING FANS ...										
Life. Life.	1	1	04	19	0.52	65	64	150	"	"
E.D. CRANE	1	1	01	7	0.44	26.5	31	200	"	"
F.D. FAN	1	1	0225	7	0.64	39	46	150	"	"
CRANKCASE EXHAUST FAN	1	1	003	3	0.36	11.2	12	100	"	"
OIL PURIFIERS	2	1	007	7	0.36	20.4	24	80	"	"
ACC. VENT FAN DB No. 1.	1	1	06	19	0.64	77.6	83	520	"	"

© 2021

Lloyd's Register

W1251004876n

All Conductors are of annealed copper conforming to British Standard Specification No. 7 (or International Electro-technical Commission Publication No. 28).

The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.

The foregoing is a correct description.

For HARLAND AND WOLFF, LIMITED

R. Green
Govan Secretary.

Electrical Engineers.

Date

COMPASSES.

Distance between electric generators or motors and standard compass *30 ft*

Distance between electric generators or motors and steering compass *25 ft.*

The nearest cables to the compasses are as follows:—

A cable carrying *20* Amperes *led into* feet from standard compass *led into* feet from steering compass.

A cable carrying *15* Amperes *15* feet from standard compass *10* feet from steering compass.

A cable carrying *20* Amperes *27* feet from standard compass *22* feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power *Yes*

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted *Yes*

The maximum deviation due to electric currents was found to be *lit* degrees on *any* course in the case of the standard compass, and *lit* degrees on *any* course in the case of the steering compass.

For HARLAND AND WOLFF, LIMITED

R. Green
Govan Secretary.

Builder's Signature.

Date

Is this installation a duplicate of a previous case *Yes* If so, state name of vessel *"BRITISH FIDELITY"*

General Remarks (State quality of workmanship, opinions as to class, &c.)

The electrical equipment of the vessel has been fitted on board under special survey, tested under full working conditions found satisfactory. The materials & workmanship are good.

RB

20/1/39

Noted

23/1/39

Total Capacity of Generators *68.* Kilowatts.

The amount of Fee ... £ *29 : 6*

When applied for,
0. 20/1/39

Travelling Expenses (if any) £

When received.

1. 2. 19 39 6 7 1/2

W. S. Macdonald
Surveyor to Lloyd's Register of Shipping.

Committee's Minute

TUE 24 JAN 1939

Assigned

See fls JE 60600



© 2021

Lloyd's Register
Foundation