

Nº 327  
MIDSHIP SECTION

DIMENSIONS: 460'-0" B.P. x 61'-0" MLD. x 33'-3" MLD TO UPPER DK.

SCALE  $\frac{1}{2}'' = 1 \text{ Foot}$

## LLOYDS NUMERALS

1<sup>st</sup> Longitudinal N° L x D 460.0" = 33.25 = 15295.00  
 2<sup>nd</sup> " " L x (B + D) 460.0 x (61.0 + 33.25) = 43355.00  
 1/2 to Upper Deck = 460.0 ÷ 33.25 = 13.83  
 D = 33.25

To Class 100A.1 at Lloyds carrying Petroleum in Bulk  
"Longitudinal Framing at Bottom and at Deck."

2 <sup>nd</sup> Long <sup>h</sup> . N° Lx(BxO)	= 43355.00
Poop 105'33"x75"x3/4	592.50
Bridge 43'16"x75"x3/4	248.70
Forecastle 38'5"x75"x3/4	216.57
House on Poop Deck 82'5"x75"÷2	309
House " Bridge " 120"x75"÷2	450
Equipment N°	45165.77

2 Bower Anchors 73% Cwts Each Stockless.  
1 Stream " 22 " Ex Stock  
240 Fathoms 2 1/2 Stud Chain Cable (Tayed)  
120 " 5 Flexible Steel Wire 6x12  
130 " 5 1/2 Special Flexible Steel Wire 6x24  
2 Bowers 100 Fathoms 2 3/4 Steel Wire 6x12  
2 Waxes 100 " 2 3/4 " " 6x12



Furness Shipbuilding Co. Ltd.

Yard no. 324.

Midship Section (as built)

S.S. "EMPIRE OIL".

MDB. RPT. No. 17038/9.

Dept. Rpt. No. 18108.



© 2020

Lloyd's Register  
Foundation

2400-82111-0042