

Rpt. 13.

No. 86846

# REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

27 FEB 1931

Received at London Office

Date of writing Report 19 When handed in at Local Office 26/2/31 Port of NEWCASTLE ON TYNE

No. in Survey held at NEWCASTLE ON TYNE Date, First Survey 18 Aug. Last Survey 13 Feb 1931  
Reg. Book. (Number of Visits 6)

90850 on the M.V. HARPA

Tons { Gross  
Net

Built at NEWCASTLE ON TYNE By whom built HAWTHORN LEWIS & CO LTD. Yard No. 575 When built 1931

Owners ANGLO-SAXON PETROLEUM CO LTD Port belonging to LONDON

Electric Light Installation fitted by HAWTHORN LEWIS & CO LTD Contract No. 575. When fitted 1931.

Is the Vessel fitted for carrying Petroleum in bulk YES

System of Distribution Double wire system

Pressure of supply for Lighting 110 volts, Heating — volts, Power 110 volts.

Direct or Alternating Current, Lighting Direct Power Direct

If alternating current system, state frequency of periods per second —

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off YES

Generators, do they comply with the requirements regarding rating YES, are they compound wound YES

are they over compounded 5 per cent. YES, if not compound wound state distance between each generator

Where more than one generator is fitted are they arranged to run in parallel NO, is an adjustable regulating resistance fitted in

series with each shunt field YES

Are all terminals accessible, clearly marked, and furnished with sockets YES, are they so spaced or shielded that they cannot be accidentally earthed,

short circuited, or touched YES Are the lubricating arrangements of the generators as per Rule YES

Position of Generators Engine Room, Starboard Side

is the ventilation in way of the generators satisfactory YES, are they clear of all inflammable material YES

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators

— and —, are the generators protected from mechanical injury and damage from water, steam or oil YES

are their axes of rotation fore and aft YES

Earthing, are the bedplates and frames of the generating plant efficiently earthed YES, are the prime movers and

their respective generators in metallic contact YES

Main Switch Boards, where placed Engine Room, Starboard Side

If the generators and main switchboard are not placed in the same compartment, is each generator provided with

a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard —

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes YES

are they protected from mechanical injury and damage from water, steam or oil YES, if situated near unprotected

woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards — and —

are they constructed wholly of durable, non-ignitable non-absorbent materials YES, is all insulation of high dielectric strength and of

permanently high insulation resistance YES, if semi-insulating material is used, are all conducting parts insulated from the slab

with mica or micanite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework YES

and is the frame effectively earthed YES Are the fittings as per Rule regarding: — spacing or shielding of live parts

YES, accessibility of all parts YES, absence of fuses on back of board YES, proportion of omnibus

bars YES, individual fuses to voltmeter, pilot or earth lamp YES, connections of switches YES

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches Double Pole Switches

+ Fuses for generators, Double Pole Change Over Switches + Fuses, also Double Pole Circuit

Breakers for Branch Circuits.


Instruments on main switchboard 2 ammeters 2 voltmeters — synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system Earth Lamps

coupled to earth through switches + fuses.

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules YES

Joint Boxes Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule YES



W1134-0013 2

**Cables:** Single, twin, concentric, or multicore single are the cables insulated and protected as per Tables IV or V of the Rules yes

**Fall of Pressure,** state maximum between bus bars and any point of the installation under maximum load 4 Volts

**Cable Sockets and other connections,** are the ends of all cables having a sectional area of 0.04 square inch and above provided with soldering sockets yes

**Paper Insulated Cables,** If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound —

**Cable Runs,** are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage yes

**Support and Protection of Cables,** state how the cables are supported and protected lead covered in accommodation, secured with brass clips, lead covered & armoured in Machinery Spaces. main cables lead covered & armoured carried in iron pipes on Deck.  
If cables are run in wood casings, are the casings and caps secured by screws —, are the cap screws of brass —, are the cables run in separate grooves —. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII yes

**Refrigerated Chambers,** if lights are fitted, are the cables and fittings in accordance with the special requirements —

**Joints in Cables,** state if any, and how made, insulated, and protected none made

**Watertight Glands and Deck Tubes,** are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands yes

**Bushes in Beams and Non-watertight Partitions,** where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed yes state the material of which the bushes are made Lead

**Earthing Connections,** state what earthing connections are fitted and their respective sectional areas none fitted  
—, are their connections made as per Rule —

**Alternative Lighting,** are the groups of lights in the propelling machinery space arranged as per Rule yes

**Emergency Supply,** state position and method of control of the emergency supply and how the generator is driven none fitted

**Navigation Lamps,** are these separately wired yes, controlled by separate switch and separate fuses yes, are the fuses double pole yes, are the switches and fuses grouped in a position accessible only to the officers on watch yes, has each navigation lamp an automatic indicator as per Rule yes

**Secondary Batteries,** are they constructed and fitted as per Rule none fitted

**Fittings,** are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight yes, are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected no

are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected yes in pump room special gastight fittings, how are the cables led —

where are the controlling switches situated in Bridge space!

**Searchlight Lamps, No. of** —, whether fixed or portable —, are their fittings as per Rule —

**Arc Lamps,** other than searchlight lamps, No. of —, are their live parts insulated from the frame or case —, are their fittings as per Rule —

**Motors,** are their working parts readily accessible yes, are the coils self-contained and readily removable for replacement yes, are the brushes, brush holders, terminals and lubricating arrangements as per Rule yes, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material yes, are they protected from mechanical injury and damage from water, steam or oil yes are their axes of rotation fore and aft yes, if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type —, if not of this type, state distance of the combustible material horizontally or vertically above the motors — and —

**Control Gear and Resistances,** are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule yes

**Lightning Conductors,** where lightning conductors are required, are these fitted as per Rule yes

**Ships carrying Oil having a Flash Point less than 150° F.** Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings yes

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office yes

**PARTICULARS OF GENERATING PLANT.**


DESCRIPTION OF GENERATOR	No. of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE	
		Kilowatts	Volts	Amps.	Rev. per Min.		Fuel Used	Flash Point of Fuel
MAIN	1	12	110	109	350	Steam Driven		
AUXILIARY	1	12	110	109	350	Kromhout Motor		
EMERGENCY								
ROTARY TRANSFORMER								

**GENERATOR, LIGHTING AND HEATING CONDUCTORS.**

DESCRIPTION	No. per Pole	CONDUCTORS Total Effective Area per Pole Sq. Ins.	COMPOSITION OF STRAND		TOTAL MAXIMUM CURRENT AMPERES		Approximate Length (Lead and Return) Feet	Insulated with	HOW PROTECTED
			No.	Diameter	In Circuit	Rule			
MAIN GENERATORS	1	0.14780	37	.072	109	152	50	V.I.R.	Lead covered & armoured
EQUALISER CONNECTIONS									
AUXILIARY GENERATOR									
EMERGENCY GENERATOR									
ROTARY TRANSFORMER									
ENGINE ROOM	1	0.03960	19	.052	27.5	64	50	"	" " " "
BOILER ROOM								"	" " " "
AUXILIARY SWITCHBOARDS									
ACCOMMODATION aft	1	0.01462	7	.052	27.5	37	80	"	" " " "
Navigation	1	0.00455	7	.029	2.0	18.2	300	"	" " " "
midship & Forward	1	0.03960	19	.052	18.6	64	290	"	" " " "
WIRELESS	1	0.01462	7	.052	30	37	80	V.I.R.	Lead covered & armoured
SEARCHLIGHT									
MASTHEAD LIGHT	1	0.00194	3	.029	.36	7.8	250	"	" " " "
SIDE LIGHTS	1	0.00194	3	.029	.36	7.8	120	"	Lead covered
COMPASS LIGHTS	1	0.00194	3	.029	.22	7.8	30	"	" " "
POOP LIGHTS									
CARGO LIGHTS	1	0.03960	19	.052	15.2	64	250	"	Lead covered & armoured
ARC LAMPS									
HEATERS									

**MOTOR CONDUCTORS.**

DESCRIPTION	No. of Motors	CONDUCTORS No. Per Pole	Total Effective Area per Pole Sq. Ins.	COMPOSITION OF STRAND		TOTAL MAXIMUM CURRENT AMPERES		Approximate Length (Lead and Return) Feet	Insulated with	HOW PROTECTED
				No.	Diameter	In Circuit	Rule			
BALLAST PUMP										
MAIN BILGE LINE PUMPS										
GENERAL SERVICE PUMP										
EMERGENCY BILGE PUMP										
SANITARY PUMP										
CIRC. SEA WATER PUMPS										
CIRC. FRESH WATER PUMPS										
AIR COMPRESSOR										
FRESH WATER PUMP										
ENGINE TURNING GEAR										
ENGINE REVERSING GEAR										
LUBRICATING OIL PUMPS										
OIL FUEL TRANSFER PUMP										
WINDLASS										
WINCHES, FORWARD										
WINCHES, AFT										
STEERING GEAR—										
(a) MOTOR GENERATOR										
(b) MAIN MOTOR										
WORKSHOP MOTOR										
VENTILATING FANS										
Lathe motor	1	1	0.00701	7	.036	16	24	60	V.I.R.	Lead covered & armoured
Spindle "	1	1	0.01046	7	.044	24	31	60	"	" " " "
Drilling "	1	1	0.00701	7	.036	16	24	60	"	" " " "
Oil separator "	1	1	0.00701	7	.036	16	24	80	"	" " " "



All Conductors are of annealed copper conforming to British Standard Specification No. 7.  
 The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.  
 The foregoing is a correct description.

FOR R. & W. HAWTHORN, LESLIE & CO. LIMITED.

*M. C. O'Mara*

Electrical Engineers.

Date 25<sup>th</sup> Feb. 1931.

COMPASSES.

Distance between electric generators or motors and standard compass 300'-0"

Distance between electric generators or motors and steering compass 295'-0"

The nearest cables to the compasses are as follows:—

A cable carrying .1 Ampères on the feet from standard compass 10 feet from steering compass.

A cable carrying .1 Ampères 10 feet from standard compass on the feet from steering compass.

A cable carrying 2 Ampères 14 feet from standard compass 8 feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power *yes*

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted *yes*

The maximum deviation due to electric currents was found to be *nil* degrees on *all* course in the case of the standard compass, and *nil* degrees on *all* course in the case of the steering compass.

FOR R. & W. HAWTHORN, LESLIE & CO. LIMITED.

*M. C. O'Mara*

Builder's Signature.

Date 25<sup>th</sup> Feb. 31.

Is this installation a duplicate of a previous case *No* If so, state name of vessel

General Remarks (State quality of workmanship, opinions as to class, &c. *This installation has been fitted on board under special survey, has been tested under working conditions and found satisfactory. The materials and workmanship were found to be good and sound.*

It is submitted that this vessel is eligible for THE RECORD.

*See Logbook  
 BT 11/3/31*

Total Capacity of Generators *24* Kilowatts.

The amount of Fee ... .. £ 19 : 10 : 0	When applied for.	12.2.19.31
	When received.	16.2.19.31.

*R. C. Clayton.*  
 Surveyor to Lloyd's Register of Shipping.

Committee's Minute

Assigned

*Elec. Lt.*

Im. 3, 30.—Transfer.  
 (The Surveyors are requested not to apply on or before the date for Committee's Minute.)



© 2020

Lloyd's Register Foundation