

M.S. "ZAANDAM" - Engine turning gear.

W1134-0141

Thomas B. Thrige

H-R/EJ.

Odense, (Denmark)

TEST-SHEET.

Order No. 75524 19 37, from Van Rietschoten & Houwens., Rotterdam.

Machine No. 229759

Type CF.16 20 H.P. 220 Volts 76,5 Amps. 750 Rev.

Armature No.: 9.394 4 Brushes No.: K.19, Dimensions 16x30, Quality F.10

tested as compound - motor enclosed ventilated Date 6/10. 1938

Hour	Terminal Volts	Line Amps.	Shunt		Rev.	Air- temp. °C	Remarks
			Volts	Amps.			
10,10	220	76,5	220	1,40	740	21	
10,20	"	"	"	1,35	750	"	
10,30	"	"	"	1,345	"	"	
10,40	"	"	"	1,31	760	"	

Temperature rise: { Armature: 18 °C, Shunt: 17 °C.  
Series-winding: 18 °C, Interpoles: 14 °C, Commutator: 12 °C

220	76,5	220	1,33	760		
"	"	"	"	"		
"	115	"	"	740	for	1 min.
"	152	"	"	700	"	30 sek.
"	4	"	1,32	820		

Insulation: { Test voltage: 2000 volts for 1 min. Starter: Not T.B.T.  
Resistance: 40 megohms.



Manufactured and tested in accordance with

Br. Lloyds rules.

SURVEYOR TO  
LLOYD'S REGISTER OF SHIPPING

*H. van der Wijk*  
16-1-39

Odense, 2/1. 1939  
pr. THOMAS B. THRIGE.

Lloyd's Register  
Foundation