

SCALE $\frac{1}{2}$ " = 1 FT.
CLASS 100 A. 1 LLOYDS

STEEL

AMENDED PLAN

CLOSED SHELTER DECK TYPE

NUMERALS

$B+D$	=	77.83
$L \times (B+D)$	=	28797
L/D TO UPPER DK.		14.09
L/D SHELTER		10.6

28797

ENGR.'S HOUSE & CASING 74x7x $\frac{1}{2}$. 259.

SALOON HOUSE $24 \times 8 \times \frac{1}{2}$: 96

EQUIPMENT NO. 31372

EQUIPMENT (x)

2 BOWERS STOCKLESS 56 $\frac{1}{4}$ CNTS EACH
1 BOWER " 47 $\frac{1}{2}$ " "
1 STREAM EX STOCK 15 " "
1 KEDGE " " 6 $\frac{1}{2}$ "
210 FMS 2 $\frac{1}{16}$ STUD CHAIN CABLE
90 FMS 4 $\frac{1}{2}$ " STEEL WIRE (STREAM)
120 " 4 $\frac{1}{2}$ " " " (TOWLINE)
2 @ 90 " 7 MANILLA (HAWSER)
2 @ 90 " 1 " (WARP)

8 x 2 1/2" ceiling fitted on tank top
in No 2 & 3 holds as required for
carrying oil fuel. Ceiling in
remainder of holds, over timbers only.

T.N. 11396

Miss's Craig Vauher Herd
No 194

Mid. Sec: as built.

Sp. Evros

Mdb upns No. 10727

n.n. Zannis L.

Cambanis

RETAIN



© 2020

Lloyd's Register
Foundation