

(LLOYDS REGISTER.)

G. R. 130
Lloyds Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyds Register of British and Foreign Shipping.

Signal Letters (if any) *J.Q.P.H.*

Official Number.		Name of Ship.		No., Date, and Port of Registry.			
140327		"Admiral bochrane"		$\frac{142}{1917}$ London.			
No., Date, and Port of Previous Registry (if any). <i>c</i>							
Whether British or Foreign Built.		Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.		Where Built.	When Built.	Name and Address of Builders.	
British		Steam Ship screw		Sunderland	1917	<i>Wm Duxford & Son Ltd.,</i> <i>Sunderland</i>	
Number of Decks <i>Two</i>		Length from fore part of stem, under the bowsprit, to the		Feet.	Tenths.
Number of Masts <i>Two</i>		aft side of the head of the stern post ...		420	-
Rigged <i>Schooner</i>		Length at quarter of depth from top of weather deck at			
Stern <i>elliptical</i>		side amidships to bottom of keel ...		420	-
Build <i>Blincher</i>		Main breadth to outside of plank ...		54	-
Galleries <i>none</i>		Depth in hold from tonnage deck to ceiling at midships ...		34	4
Head <i>straight</i>		Depth in hold from upper deck to ceiling at midships, in the			
Framework and description of		... <i>steel</i>		case of three decks and upwards ...		-	-
vessel <i>bargo</i>		Depth from top of beam amidships to top of keel ...		38	08
Number of Bulkheads <i>seven</i>		Depth from top of deck at side amidships to bottom of keel		37	25
Number of water ballast tanks, <i>Seven</i> =				Round of beam ...		1	08
and their capacity in tons ...		<i>1383 tons</i>		Length of engine room, if any ...		49	8

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel... *13977* Tons. Ditto per inch immersion at same depth... *45.09* Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.		
One	Reciprocating, triple expansion, Direct Acting	Engines.	Engines.	Engines.	Three			572
		&	&	&	27"			
	Particulars of Boilers.	Boilers.	Boilers.	Boilers.	45"	54"		2400
	Description: Multitubular			North Eastern Marine Eng Co. Ltd., Wallsend	74"			11 knots
One	Number: Three	British	1917					
	Iron or Steel: Steel							
	Loaded Pressure: 180 lbs							

PARTICULARS OF TONNAGE.

GROSS TONNAGE.		No of Tons.	DEDUCTIONS ALLOWED.		No. of Tons.
Under Tonnage Deck ...		6294.27	On account of space required for propelling power		2100.68
Space or spaces between Decks...			On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew		
Turret or Trunk ...			These spaces are the following, viz.:-		
Forecastle ...			Officers, Engineers & crew space		188.02
Bridge space ...		8.33	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:-		
Poop or Break ...		137.79	Cubic Metres		
Side Houses ...		8.09	Master's Accom 15.24		
Deck Houses ...		45.87	Booms Stores 50.25		
Chart House ...		70.27	Chart Ho. 8.09		146.57
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ...			Wireless Tel. Ho 3.45		
Excess of Hatchways ...			Water Ballast 69.54		
Gross Tonnage ...		6564.62	Total } 2435.27		
Deductions, as per Contra ...		2435.27			
Registered Tonnage ...		4129.35			

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is *819.24* tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is *46.67* tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Name of Master		Certificate of { Service No. Competency No.			
No. of Owners					
Name, Residence, and Description of Managing Owner if there are more owners than one.					
<i>Byron Steamship Company Ltd.,</i> <i>of Holland House, Bury Street,</i> <i>London E.C.3</i> <i>64 Shares</i>		<i>Michael Andreas Embiricos,</i> <i>Holland House, Bury Street,</i> <i>London E.C.3</i> <i>is Manager</i>			
Dated <i>9th August 1917</i>					