

DIMENSIONS 425'-0" B.P. x 54'-3" x 31'-0" MOULDED.

LLOYDS NUMERALS.

D	31.
$L \times D$	425×31 13175.
$L \times (B + D)$	$425 \times (5425 + 31)$ 36231.
L/D	$425/31$ 13.7.

ALL BULB ANGLES ARE NEW BRITISH STANDARD.

EQUIPMENT NUMBER.

<u>L × (B + D)</u>		36231.
<u>POOP</u>	90.625	
<u>BRIDGE</u>	40.680	
<u>FORECASTLE</u>	65.41	
	<u>196.715</u>	× 7.5 × 75.
<u>BRIDGE DECKHOUSE</u>	34.5 × 75 × 50.	1106
<u>CASINGS ETC.</u>	74.5 × 75 × 50.	289
		<u>37,755</u>

EQUIPMENT.

3 BOWER ANCHORS 64.83 CWTs EACH STOCKLESS.
1 STREAM ANCHOR 19 CWTs. (EX. STOCK).
270 FATHOMS 2 3/8" DIAMETER STUD CHAIN CABLE.
90 FATHOMS 5" S.W.R. STREAM LINE.
120 FATHOMS 4 3/4" S.W.R. TOWLINE.
2 @ 90 FATHOMS 3 3/4" S.W.R. HAWSERS. (RULE 2 3/4")
2 @ 90 FATHOMS 3 1/4" S.W.R. WARPS. (RULE 2 1/2")

Harland & Wolff. Ltd

981 G.

M.V. SITALA

Midship Section (As built)

GLASGOW REPORT No 58157

961/2

Sister Vessels :-

No 961 "Scandella" Gls Rpt 56890

962 "Simnia" " 56980



© 2020

Lloyd's Register

W1142-0142