

Industria 36243

T. O. closed (W. E.)

Index. No. 36002  
(For London Office only).

# Lloyd's Register of Shipping.

## SURVEYS FOR FREEBOARD.

(COMPUTATION FOR STEAMER, SAILING SHIP, TANKER.)

Ship's Name <b>ELMDENE</b>	Official Number <b>167371</b>	Nationality and Port of Registry <b>British, London</b>	Gross Tonnage	Date of Build <b>1939</b> <b>11 mo.</b>	Port of Survey
Moulded Dimensions: Length <b>406.52'</b> Breadth <b>56.0'</b> Depth <b>36.37'</b>					Date of Survey <b>31.3.41</b>
Moulded displacement at moulded draught = 85 per cent. of moulded depth tons					Surveyor's Signature
Coefficient of fineness for use with Tables					Particulars of Classification <b>+100A1</b> <b>with freeboard.</b>

<b>Depth for Freeboard (D).</b> Moulded depth ... <b>36.37</b> Stringer plate ... <b>51</b> Sheathing on exposed deck $T \left( \frac{L-S}{L} \right) =$ Depth for Freeboard (D) = <b>36.41</b>	<b>Depth correction.</b> (a) Where D is greater than Table depth (D - Table depth) R = <b>.04</b> (b) Where D is less than Table depth (if allowed) (Table depth - D) R = If restricted by superstructures	<b>Round of Beam correction.</b> Moulded Breadth (B) Standard Round of Beam = $\frac{B \times 12}{50} =$ Ship's Round of Beam = Difference Restricted to Correction = $\frac{\text{Diff}^e}{4} \times \left( 1 - \frac{S_1}{L} \right) =$
--	--	---

## DEDUCTION FOR SUPERSTRUCTURES.

	Mean Covered Length (S)	Equivalent Enclosed Length (S <sub>1</sub> )	Height	Height Correction	Effective Length (E)
Poop enclosed ...					
„ overhang ...					
R.Q.D. enclosed ...					
„ overhang ...					
Bridge enclosed ...					
„ overhang aft ...					
„ overhang forward ...					
Fore enclosed ...	<b>33.875</b>	<b>33.875</b>	<b>7.0</b>		
„ overhang ...					
Trunk aft ...					
„ forward ...					
Tonnage opening aft ...					
„ „ forward ...					
Total ...					

Standard Height of Superstructure  
 „ „ R.Q.D.  
 Deduction for complete superstructure  
 Percentage covered  $\frac{S}{L} =$   
 „  $\frac{S_1}{L} =$   
 „  $\frac{E}{L} =$   
 Percentage from Table, Line A.  
 (corrected for absence of forecastle (if required))  
 Percentage from Table, Line B.  
 (corrected for absence of forecastle (if required))  
 Interpolation for bridge less than .2L (if required)  
 Deduction =

## SHEER CORRECTION.

Station	Standard Ordinate	S	M	Product	Actual Ordinate	Effective Ordinate	S	M	Product
A.P. ...		1					1		
$\frac{1}{4}L$ from A.P. ...		4					4		
$\frac{3}{4}L$ „ ...		2					2		
Amidships ...		4					4		
$\frac{3}{4}L$ from F.P. ...		2					2		
$\frac{1}{4}L$ „ ...		4					4		
F.P. ...		1					1		
Total ...									

Mean actual sheer aft =  
 Mean standard sheer aft =  
 Mean actual sheer forward =  
 Mean standard sheer forward =  
 Length of enclosed superstructure forward of amidships =  
 „ „ aft of „ =

$$\text{Correction} = \frac{\text{Difference between sums of products}}{18} \left( \frac{75 - S}{2L} \right) =$$

If limited on account of midship superstructure.

If limited to maximum allowance of  $1\frac{1}{2}$  ins. per 100 ft.

## Deduction for Tropical Freeboard.

## Addition for Winter and Winter North Atlantic Freeboard.

$$\begin{aligned} \text{Depth to Freeboard Deck} &= \text{Ft. } 36.41 \\ \text{Summer freeboard} &= 10.58 \\ \text{Moulded draught (d)} &= 25.83 \end{aligned}$$

## Deduction for Tropical freeboard and addition for

$$\text{Winter freeboard} = \frac{d}{4} \text{ inches} = 6.46 = 6\frac{1}{2}$$

## Addition for Winter North Atlantic Freeboard (if required)=

## Deduction for Fresh Water.

Displacement in salt water at summer load water line

$$\Delta =$$

Tons per inch immersion at summer load water line

$$T =$$

$$\text{Deduction} = \frac{\Delta}{40T} \text{ inches}$$

$$= 7''$$

## TABULAR FREEBOARD corrected for Flush Deck (if required)

Correction for coefficient

	+	-
Depth Correction ...		
Deduction for superstructures ...		
Sheer correction ...		
Round of Beam correction ...		
Correction for Thickness of Deck amidships ...		
Other corrections, scantlings, etc. to correspond to a summer moulded draught of 25'-10"		

Summer Freeboard =

## SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, Steel, Deck:

Tropical Fresh Water Line above Centre of Disc	13 1/2"
Fresh Water Line	7"
Tropical Line	6 1/2"
Winter Line below	6 1/2"
Winter North Atlantic Line	✓

Tropical Fresh Water Freeboard	9'-5 1/2"
Fresh Water	10'-0"
Tropical	10'-0 1/2"
Winter	11'-1 1/2"
Winter North Atlantic	✓

4 APR 1941

W1144 - 0020

Lloyd's Register Foundation

14/5/41