

WOKINGHAM.

COPY.

Lloyd's Register of Shipping.



Port

NEWCASTLE ON TYNE.

17th March 1941.

This is to Certify that

W. E. MARLBOROUGH,

the undersigned Surveyor to this Society did at the request of the Owners' Representative, survey the steamer "KENNETH HAWKSFIELD", 1546 tons gross, of Dover, whilst lying afloat at Jarrow-on-Tyne on the 24th February 1941 and subsequently, in order to ascertain the nature and extent of damage stated to have been sustained by collision with s.s. "AFON DULAIS" while in convoy off the Nore Light Vessel on the 1st February 1941 on a voyage Blyth to Dover.

FOUND:-

In way of After Hold and Port Side, Shell and Deck Plating, Framing etc. more or less badly indented.

RECOMMENDED:-

- In way of After Hold and Port Side Main Sheer Strake, one plate to be renewed.
1st Strake below Sheer, one plate to be removed, faired and refitted.
2nd Strake below Sheer, one plate to be faired in place.
1 Deck Stringer Plate to be renewed by two plates.
1 Deck Stringer Angle to be renewed.
1 Bulb Angle Deck Longitudinal to be faired in place.
1 Main Frame to be cropped and part renewed, the butt electric welded, and back bar fitted.
2 Main Frames to be faired in place.
1 Frame Knee and Connection Bar to Deck Stringer Plate to be renewed.
1 Bulwark Plate to be renewed, and one to be faired in place.
Bulwark Rail Bar entangled with Stays, to be removed, faired, and refitted.
1 length of wash deck pipe to be renewed.

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:—

"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."

COPY.

- 2 -

s. "KENNETH HAWESFIELD".

17th March 1941.

1 Mooring Bollard to be renewed.

All disturbed work to be replaced or part renewed as necessary.

The foregoing recommendations were made in

order to place the vessel in the same satisfactory condition as prior
to the casualty.

A. E. Marlborough.

SURVEYOR TO LLOYD'S REGISTER.

NEWCASTLE ON TYNE.



© 2020

Lloyd's Register
Foundation

W1145-0036²/₂