

CLASS CONTEMPLATED.

(LLOYD'S REGISTER.)

G.R. 130.
Lloyd's Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.
Signal Letters (if any) G.Y.F.R.

Official Number.	Name of Ship.	No., Date, and Port of Registry.
164,047.	Darcolm.	6/1935 Glasgow.

No., Date, and Port of Previous Registry (if any). -----

Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Ship Single Screw.	Port Glasgow.	1935	Wm. Hamilton & Co., Ltd., Port Glasgow.
Number of Decks ..	One & Shelter	Length from fore part of stem, under the bowsprit, to the	Feet.	Tenths.
Number of Masts ..	Two	aft side of the head of the stern post	390	0
Rigged	Schooner	Length at quarter of depth from top of weather deck at side	388	3
Stern	Elliptical	amidships to bottom of keel	53	0
Build	Clincher	Main breadth to outside of plank	24	7
Galleries	None	Depth in hold from tonnage deck to ceiling at midships ..	--	--
Head	None	Depth in hold from upper deck to ceiling at midships, in the	28	2.5
Framework and description of vessel	Steel Cargo	case of three decks and upwards	27	4
Number of Bulkheads ..	Six	Depth from top of beam amidships to top of keel	1	0.8
Number of water ballast tanks, and their capacity in tons ..	Six in D.B. 114 Fore Peak 153 Tons Aft Peak 125 Tons	Round of beam	47	5
		Length of engine room, if any		

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel .. 9100 Tons. Ditto per inch immersion at same depth .. 39.74 Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. I. H. P. Speed of Ship.
One	Reciprocating Steam Triple Expansion Vertical.	Engines.	Engines.	Engines.	Three			180
No. of Shafts.	Particulars of Boilers.				25"	48"		2000
	Description .. Cylindrical Multitubular	Boilers.	Boilers.	Boilers.	38"			
One	Number .. Three	British	1935	John G. Kincaid & Co., Ltd., Greenock.	70"		10 knots	
	Iron or Steel .. Steel							
	Loaded Pressure .. 200 lbs/sq"							

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	4033.04	On account of space required for propelling power	1374.89
Space or spaces between Decks		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	169.81
Turret or Trunk	21.25	These spaces are the following, viz.:— Spaces in Poop and in Houses above upper deck. (Number of Seamen or Apprentices for whom accommodation is certified... 42.....)	
Forecastle .. (Lower)		Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Bridge space	97.04	Master's Accommodation 10.93	
Poop or Break		Chart Space 3.88	
Side Houses	141.32	Wireless Telegraphy Space 2.82	148.46
Deck Houses	3.88	Boatswains Store 42.97	
Chart House		Water Ballast Spaces 87.86	
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894			
Excess of Hatchways			
		Cubic Metres.	
Gross Tonnage	4296.53	12159.18	
Deductions, as per Contra	1693.16	4791.64	
Register Tonnage	2603.37	7367.54	1693.16

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 573.53 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 113.92 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Space in Shelter 'Tween Decks 333.7 feet in length - 1148.94 Tons.
" " " Upper Forecastle 29.7 " " " - 47.79 Tons.

Name of Master	Certificate of { Service Competency No.
No. of Owners	
Name, Residence, and Description of Managing Owner if there are more owners than one.	
Nearco Shipping Company, Limited, 45, West Nile Street, Glasgow, C.1. Sixty-four Shares.	Bryce Buchanan Ramsey of same address—Manager.
Dated 9 Mar. 1935.	