

COPY.

Lloyd's Register of Shipping.



FREMANTLE. W.A.

Port

9th May, 1941.

This is to Certify that
WM.G. DAVIES,

the undersigned Surveyor to this Society did at the request of the Master and Agents, survey the Steel Screw Steamer "MARBORA" of Melbourne 3472 Gross Registered tons for the purpose of (1) arranging location and type of additional scuppers on Freeboard Deck consequent upon the vessel being equipped for carrying Sheep and/or Cattle in the Shelter Deck spaces and (2) carrying out and Annual Freeboard Survey.

RECOMMENDED that:-

- (1) Four Scuppers consisting of 3" (three inch) heavy steam flanged standard bends be fitted in the Freeboard Deck and leading overboard through the sheerstrake. The outer ends of the bends to act as a spigot to be electrically welded to the Hull plating. Two of the scuppers were fitted abreast the after end of No.2 Hatch and two abreast the forward end of No.4 Hatch on Port and Starboard sides.
- (2) To prevent cattle waste and water affecting the bottom insulation of the Refrigerator Chambers and from leaking through a wooden bulkhead into the side bunkers; steel plates 9" (nine inches) high by 1/2" (half inch) thick be fitted to extend each side from a deep frame at sides to the screen bulkhead of a midship housing. These plates to be welded to the deck and filled in behind with cement and thus made watertight.

Items Nos. 1 & 2 have been satisfactorily completed and tested and at the same time newly jointed Cargo doors in the ship's sides in way of the Shelter Deck space were "hose" tested and all found tight and an Interim Certificate has been issued. The testing of the doors was part of the Annual Freeboard Survey. Existing Scuppers were also "hose" tested and found good.

Wm. G. Davies.

SHIP & ENGINEER SURVEYOR
TO LLOYD'S REGISTER OF SHIPPING.

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:-

"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."