

# REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

18 OCT 1924

Date of writing Report 19... When handed in at Local Office 16.10.1924 Port of Middlesbrough

No. in Survey held at Stockton Date, First Survey April Last Survey December 19  
Reg. Book. (Number of Visits.....)

on the S.S. REEDPOOL Tons { Gross -  
Net -

Built at Stockton By whom built Ropner S.B. & Co Yard No. 545 When built 1924

Owners Messrs R Ropner & Co Port belonging to Stockton-on-Tees

Electric Light Installation fitted by Messrs Jukergall & Sons Contract No. When fitted

System of Distribution Double Wire

Pressure of supply for Lighting 100 volts, Heating - volts, Power - volts.

Direct or Alternating Current, Lighting Direct Power -

If alternating current system, state frequency of periods per second -

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off Yes

Generators, do they comply with the requirements regarding overload Yes, are they compound wound Yes

are they over compounded 5 per cent. - , if not compound wound state distance between each generator

Where more than one generator is fitted are they arranged to run in parallel - , is an adjustable regulating resistance fitted in series with each shunt field Yes

Are all terminals accessible and clearly marked Yes, are they so spaced or shielded that they cannot be accidentally earthed, or short circuited Yes

Position of Generators Starboard side of ship, are they so spaced or shielded that they cannot be accidentally earthed, or short circuited Yes

is the ventilation in way of the generators satisfactory Yes, are they clear of all inflammable material Yes

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators 4'-0" and Asbestos Liner are the generators protected from mechanical injury and damage from water, steam or oil

are their axis of rotation fore and aft Yes

Earthing, are the bedplates and frames of the generating plant efficiently earthed Yes are the prime movers and their respective generators in metallic contact Yes

Main Switch Boards, where placed on Starboard side Engine Room w. Generators

If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes Yes

are they protected from mechanical injury and damage from water, steam or oil Yes, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards 1'-0" and Asbestos Liner

are they constructed wholly of durable, incombustible non-absorbent materials Yes, is all insulation of high dielectric strength and of permanently high insulation resistance Yes

if semi-insulating material is used, are all conducting parts connected to one pole insulated from the slab with mica or micanite and the slab similarly insulated from its framework Yes

frame effectively earthed Yes. Are the following fittings as per Rule, viz. :- spacing or shielding of live parts

Yes, accessibility of all parts Yes, absence of fuses on back of board Yes, proportion of omnibus bars Yes

Yes, individual fuses to voltmeter, pilot or earth lamp Yes, connections of switches Yes

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches

Main Double Pole Switch with Single Pole Circuit Switches & Double Pole Fuses to various Distribution Stations

Instruments on main switchboard 1 ammeters 1 voltmeters synchronising device for paralleling purposes

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system Earth Ramps


Each Pole

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules Yes

Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule Yes

Engine Room, Iron Frame, Asbestos Liner, Accommodation Deck Cases

Asbestos Liner



**Insulation of Cables**, state type of cables, single or twin Single are the cables insulated and protected as per Tables III or IV of the Rules. yes

**Fall of Pressure**, state maximum between bus bars and any point of the installation under maximum load.

**Cable Sockets and other connections**, are the ends of all cables having a sectional area of 0.007 square inch and above provided with soldering sockets yes

**Paper Insulated Cables**. If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound.

**Cable Runs**, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage yes

**Support and Protection of Cables**, state how the cables are supported and protected? By Iron clips lead covered & armoured in Engine Room, Hoists, Accommodation lead covered & Brass clips

If cables are run in wood casings, are the casings and caps secured by screws, are the cap screws of brass, are the cables run in separate grooves. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VI yes

**Refrigerated Chambers**, if lights are fitted, are the cables and fittings in accordance with the special requirements

**Joints in Cables**, state if any, and how made, insulated, and protected none

**Watertight Glands and Deck Tubes**, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands yes

**Bushes in Beams and Non-watertight Positions**, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed. state the material of which the bushes are made Lead

**Earthing Connections**, state what earthing connections are fitted and their respective sectional areas Main Switch Board & Generator

are their connections made as per Rule

**Alternative Lighting**, are the groups of lights in the propelling machinery space arranged as per Rule yes

**Emergency Supply**, state position and method of control of the emergency supply and how the generator is driven none

**Navigation Lamps**, are these separately wired yes, controlled by separate switch and separate fuses yes

are the fuses double pole, are the switches and fuses grouped in a position accessible only to the officers on watch

has each navigation lamp an automatic indicator as per Rule yes, are separate screens provided for the use of oil and electric side lights yes

are separate oil lanterns provided for the mast head lights and side lights ✓

**Fittings**, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight yes

are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected no

are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected no

how are the cables led

where are the controlling switches situated

**Searchlight Lamps**, No. of none, whether fixed or portable, are their fittings as per Rule

**Arc Lamps**, other than searchlight lamps, No. of, are their live parts insulated from the frame or case, are their fittings as per Rule

**Motors**, are their working parts readily accessible, are the coils self-contained and readily removable for replacement

are the brushes, brush holders, terminals and lubricating arrangements as per Rule, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material

are they protected from mechanical injury and damage from water, steam or oil, are their axis of rotation fore and aft

if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type, if not of this type, state distance of the combustible material horizontally or vertically above the motors and

**Control Gear and Resistances**, are the generator field and motor speed regulators, starters and controllers constructed as per Rule

**Lightning Conductors**, where lightning conductors are required, are these fitted as per Rule yes

**Ships carrying Oil having a Flash Point less than 150° F.** Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings.

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office

PARTICULARS OF GENERATING PLANT.									
DESCRIPTION OF GENERATOR.	No of	RATED AT				DRIVEN BY.	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.		
		Kilowatts.	Volts.	Ampères.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.	
MAIN	1	7 <sup>3</sup> / <sub>4</sub>	100	77 <sup>1</sup> / <sub>2</sub>	550	Engine by Messrs. W. & A. S. Beard.			
AUXILIARY									
EMERGENCY									
ROTARY TRANSFORMER									

LIGHTING AND HEATING CONDUCTORS.									
Ref. No.	DESCRIPTION.	No. of Conductors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Amperes.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	MAIN GENERATOR...	2	0.450	19	.072	77.5	13 ft	Rubber	Leaded
	AUXILIARY GENERATOR								
	EMERGENCY GENERATOR								
	ROTARY TRANSFORMER...								
	AUXILIARY SWITCHBOARDS								
	ENGINE ROOM	2	0.100	7	.044	10.0	50 ft	"	Leaded
	BOILER ROOM	2	0.030	3	.036	5.0	120 ft	"	Do
	Engineers Accommodation	2	0.100	7	.044	10.0	80 ft	"	Do
	Officers - 150	2	0.145	7	.052	14.5	160 ft	"	Do
	WIRELESS	2	0.100	7	.044	10.0	165 ft	Rubber	Leaded
	SEARCHLIGHT								
	MASTHEAD LIGHT	2	0.030	3	.036	5.0	100 ft	"	"
	SIDE LIGHTS	2	0.015	1	.044	1.5	38 ft	"	"
	COMPASS LIGHTS	2	0.015	1	.044	1.5	14 ft	"	"
	POOP LIGHTS	2	0.100	7	.044	10.0	264 ft	"	"
	CARGO LIGHTS	2	0.100	7	.052	14.5	130 ft	"	"
	ARC LAMPS								
	HEATERS								

MOTOR CONDUCTORS.									
Ref. No.	DESCRIPTION.	No. of Motors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Amperes.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	BALLAST PUMP								
	MAIN BILGE LINE PUMPS								
	GENERAL SERVICE PUMP								
	EMERGENCY BILGE PUMP								
	SANITARY PUMP								
	CIRC. SEA WATER PUMPS								
	CIRC. FRESH WATER PUMPS								
	AIR COMPRESSOR								
	FRESH WATER PUMP								
	ENGINE TURNING GEAR								
	ENGINE REVERSING GEAR								
	LUBRICATING OIL PUMPS								
	OIL FUEL TRANSFER PUMP								
	WINDLASS								
	WINCHES, FORWARD								
	WINCHES, AFT								
	STEERING GEAR								
	WORKSHOP MOTOR								
	VENTILATING FANS								

All Conductors are of annealed copper conforming to British Standard Specification No. 7.  
 The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.  
 The foregoing is a correct description.

RICHARD PICKERSGILL & SONS, LTD.

*Richard Pickersgill*

Electrical Engineers.

Date *October 4<sup>th</sup> 1924*

COMPASSES.

Distance between electric generators or motors and standard compass *230 ft*  
 Distance between electric generators or motors and steering compass *230 ft*  
 The nearest cables to the compasses are as follows:—  
 A cable carrying *5* Ampères *10* feet from standard compass *16* feet from steering compass.  
 A cable carrying *.75* Ampères *12* feet from standard compass *16* feet from steering compass.  
 A cable carrying *.75* Ampères *12* feet from standard compass *16* feet from steering compass.  
 Have the compasses been adjusted with and without the electric installation at work at full power *yes*  
 Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted *yes*  
 The maximum deviation due to electric currents was found to be *20* degrees on *all* course in the case of the standard compass, and *10* degrees on *all* course in the case of the steering compass.

FOR THE ROPNER SHIPBUILDING AND REPAIRING CO. (STOCKTON) LIM.

*H. J. Gornall*  
Secretary.

Builder's Signature.

Date *Oct 11/1924*

Is this installation a duplicate of a previous case *no* If so, state name of vessel *✓*

General Remarks (State quality of workmanship, opinions as to class, &c. *This installation has been fitted in accordance with the Rules: is of good materials & workmanship and on completion was examined under full working conditions & found satisfactory.*

*It is submitted that this vessel is eligible for THE RECORD.*  
*Elec. Light.*  
*W. J.*  
*20/10/24*

Total Capacity of Generators *73* Kilowatts

The amount of Fee ...	£ <i>7-15-0</i>	} When applied for, 3.10.1924
Travelling Expenses (if any) £	<i>✓</i>	

*Wm Morrison*  
Surveyor to Lloyd's Register of Shipping.

Committee's Minute

Assigned

5c.1243.—Transfer.  
(The Surveyors are requested not to write on or below the space for Committee's Minute.)



© 2020

Lloyd's Register Foundation