

# (LLOYD'S REGISTER.)

G.R. 130  
Lloyd's Register.

## VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.  
Signal Letters (if any) K, R, L, J.

Official Number.	Name of Ship.	No., Date, and Port of Registry.
135,609.	REEDPOOL.	6/1924. Stockton.

No., Date, and Port of Previous Registry (if any). -----

Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steamship Single Screw.	Stockton-on-Tees	1924	Ropner Shipbuilding & Repairing Company (Stockton) Ltd Stockton-on-Tees.

Number of Decks ... .. One	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ... ..	Feet.	Tenths
Number of Masts ... .. Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ... ..	390	0
Rigged ... Fore & Aft. No sails	Main breadth to outside of plank ... ..	390	0
Stern ... .. Elliptical	Depth in hold from tonnage deck to ceiling at midships ...	55	5
Build ... .. Clincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ... ..	26	4
Galleries ... .. None	Depth from top of beam amidships to top of keel ... ..	29	9.1
Head ... .. None	Depth from top of deck at side amidships to bottom of keel	28	9.5
Framework and description of Steel Cargo vessel ... ..	Round of beam ... ..	1	1.6
Number of Bulkheads ... Six. Watertight	Length of engine room, if any ... ..	49	6.
Number of water ballast tanks, Seven and their capacity in tons .1415 Tons			

### PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ... ..	10324 Tons.	Ditto per inch immersion at same depth ... ..	42.64 Tons.
---	-------------	---	-------------

### PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.	No. of Cylinders in each set.	
One	Vertical triple compound direct acting triple expansion	Engines.	Engines.	Engines.	Three 26" 43" 71"	48"	-----	437 2,000
One	Cylindrical Three Steel Loaded Pressure...180 lbs. per sq. inch	Boilers.	Boilers	Boilers.	Blair & Co., Ltd., Stockton-on-Tees.			10 Knots


### PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ... ..	4609.52	On account of space required for propelling power	1548.31
Space or spaces between Decks... ..	.12	On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	151.31
Expansion Trunk	72.11	These spaces are the following, viz.:—	
Forecastle ... ..	4.68	Forecastle and Round Houses	
Bridge space ... ..	113.59	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Poop or Break ... ..		Master's accommodation 6.97	
Side Houses ... ..	38.45	Boatswain's Store 20.94	
Deck Houses Round Houses ... ..		Wireless Room 4.50	145.13
Chart House ... ..		Chart Space 7.30	
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ... ..		Fore peak Tank 45.83	1844.75
Excess of Hatchways ... ..		After peak Tank 59.49	
Gross Tonnage ... ..	4838.47	Cubic Metres	
Deductions, as per Contra ... ..	1844.75	13692.87	
Register Tonnage ... ..	2993.72	5220.64	
		8472.23	

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 680.82 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 126.07 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Bridge Space	Length	220.2'	=	752.32 Tons
Open Poop Space	Length	38.0'	=	104.01 -"



Name of Master Thomas Morgan Hill Certificate of { Service -- Nor Competency No. 002833

No. of Owners  
Name, Residence, and Description of Managing Owner if there are more owners than one.

The Pool Shipping Company Limited  
having its principal place of business at West Hartlepool, in the County of Durham  
Sixty-four (64) Sixty-fourth Shares.  
William Ropner of Mercantile Chambers, Mainsforth Terrace, West Hartlepool, -Manager.

Dated 26 September, 1924.

