

COPY. GLASGOW

LONDON

15th June, 1937

Dear Sirs,

Yard No.424

I have to acknowledge the receipt of your letter of the 14th instant, the contents of which have been noted, and with regard thereto I have to inform you that the web frame in the hold may be fitted at frame 106 as desired by the Owners instead of at frame 116 as indicated on the plan of Profile. This web frame should be 36" deep instead of 24" as proposed.

Further I have to state that if the tubular pillars be made of weldless rolled or drawn steel with tensile strength 35/41 tons per square inch, the thicknesses as shown on the approved Pillar & Girder plan may be reduced by 10%.


I am, Dear Sirs,

Yours faithfully,

Local Secretary.

Messrs. Chas. Connell & Co., Ltd.,

SCOTSTOWN.



Lloyd's Register
Foundation

W116-0034