

G.R. 130.

89823 2

CLASS CONTEMPLATED.

(LLOYD'S REGISTER.)

VESSELS OF 100 TONS AND UPWARDS.



These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping.

Signal Letters (if any) G.R.R.K.

Official Number.	Name of Ship.	No., Date, and Port of Registry.
<u>167199</u>	ROWALLAN CASTLE	57 in 1939, London.

No., Date, and Port of previous Registry (if any).

Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Motor Ship Single Screw	Belfast	1939 FE	Harland & Wolff Ltd., Belfast.

Number of Decks ...	Four	Length from fore part of stem, to the aft side of the head of the stern post ...	Feet.	Tenths.
Number of Masts ...	Two		457	4
Rigged ...	Not	Main breadth to outside of plank ...	63	3
Stem ...	Straight	Depth in hold from tonnage deck to ceiling amidships ...	18	1.5
Stern ...	Cruiser	Depth in hold from upper deck to ceiling amidships, in the case of three decks and upwards ...	34	3
Build ...	Glencher	Depth from top of deck at side amidships to bottom of keel	37	3
Framework and description of vessel ...	Steel Cargo	Round of beam ...	1	2.7
Number of Bulkheads ...	Seven	Length of engine room, if any ...	63	-

Particulars of propelling Engines, etc. (if any), and Water Ballast Tanks, as supplied by Builders, Owners, or Engine Makers.

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N.H.P. B.H.P. I.H.P. Estimated Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.		
One	Internal Combustion Direct Acting Vertical Two Stroke Double Acting	British	1939	Harland & Wolff Ltd., Belfast.	Eight	620 m/m.	1400 m/m.	858
One	Vertical Multitubular Boilers.	British	1939	Cochran & Co. (Annan) Ltd., Annan.	24 2/16	55 1/8	-	7500 9270 16 Knots

Number of water ballast tanks, and their capacity in tons:— Seven = 1493 Tons.  
Fore Peak 46 Tons. Aft Peak 126 Tons.

PARTICULARS OF TONNAGE.


GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...	3354.78	On account of space required for propelling power	2495.33
Space or spaces between Decks ...	3608.58	On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from Goods or Stores of every kind, not being the personal property of the Crew	
Turret or Trunk ...	6963.36	These spaces are the following, viz:—	405.21
Forecastle and Houses in ...	16.38	In Bridge and Deckhouses.	
Bridge space ...	534.58	(Number of Seamen or Apprentices for whom accommodation is certified 64 ...)	
Poop or Break ...		Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Side Houses ...	265.82	Chart Space 7.51	
Deck Houses ...	7.51	Masters Accommodation 15.87	
Chart House ...		Wireless Telegraphy Space 6.55	169.74
Spaces for Machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ...		Boatswains Stores 35.25	
Excess of Hatchways ...	10.27	Water Ballast Spaces: ...	3070.28
Gross Tonnage ...	7797.92	F.P. 10.29	
Deductions, as per contra ...	3070.28	A.P. 37.05	
Register Tonnage ...	4727.64	Steering Gear Spaces 57.22	

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 1069.36 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 211.95 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

In Forecastle	Length 32.5 Ft. = 57.71 Tons.
In Bridge - Open Space Aft End (S)	" 7.8 " = 4.06 "
On Navigation Bridge P. & S. Lookout Houses	" 5.2 " = 3.52 "

Name of Master	Certificate of { Service No. Competency No.
No. of Owners	
Name, Residence, and Description of Managing Owner if there are more owners than one.	
The Union-Castle Mail Steamship Co. Ltd., 3, Fenchurch St., London, E.C.3.	Managers: Arthur Henry Milbourne and Isaac Jabez Newcombe, both of 3, Fenchurch St., London, E.C.3., and Frederick Charles Victor Yarrow, Canute Rd., Southampton.
Shares: Sixty-four.	
Dated 1st March, 1939.	



W116-0091

Mr. Eden

REGISTERED COPY



© 2019

Lloyd's Register  
Foundation

This record is related to the Mr. Richmond Castle (Belmont Report N: 12312)