

COPY



SYDNEY, N.S.W.

16th January 1943.


A.J. McCOWAN & A.A. QUANT

Messrs. Port Line Ltd., Lloyd's Agents,
and with the consent of the Owners Representatives, attend on board
the M.S. "CANADIAN STAR", of London, 8293 tons gross,
afloat at Pyrmont berth, Sydney Harbour, on the 10th inst., and
subsequent dates for the purpose of examining the vessel for damage
stated to have been caused by stress of weather during the voyage
from Suez to Sydney via Fremantle.

For further particulars see Log Book, from which it would
appear that the vessel in ballast encountered heavy weather from
the 24th December 1942 to the 2nd January 1943 and that leakage of
fuel oil from the port settling tank in engine room was subsequently
found at the forward bulkhead of No. 4 insulated hold.

ON EXAMINATION FOUND:- Evidence of leakage at the bottom of the
insulated bulkhead, forward end of No. 4 hold, port side where the
insulation was saturated with fuel oil.

As recommended, sufficient insulation was removed from the bulkhead
and tank top in way, where the leakage was found from a slack rivet
in the bulkhead stiffener.



© 2020

Lloyd's Register
Foundation

- 2 -

M.S. "CANADIAN STAR"

(Continued)

AS RECOMMENDED AND NOW DONE:- As it was not possible to "gas-free" the port settling tank in engine room without considerable expense and delay to the vessel, it was ^{recommended} as a temporary repair, that the slack rivet be removed and replaced by a countersunk "tap-screw" from the hold side. The settling tank was then tested with a head of water and found tight.

The bulkhead was cleaned, all traces of fuel oil removed and all damaged insulation renewed, as originally. Whilst these repairs were in progress, the compartment was well ventilated in order to remove fumes or taint from the fuel oil leakage and, on completion, considered fit for the carriage of refrigerated cargo.

It is further recommended that permanent repairs to this bulkhead be effected at first convenient opportunity.

(Sgd.) A.J.McCOWAN.

(Sgd.) A. A. QUANT (Acting)

SURVEYORS TO LLOYD'S REGISTER.



© 2020

Lloyd's Register
Foundation