

COPY.

# Lloyd's Register of Shipping,

71, Fenchurch Street, E.C. 3.

26th April, 1939.

Dear Sir,

E.

I duly received your letter of the 20th instant, with enclosures, relating to the electrical installation proposed by Messrs. W.M. Goodfellow & Co. Ltd. for Messrs. Lithgows' Yard No.906.

The plan submitted has been examined, and with regard thereto I have to inform you that no objection will be taken to the use of Pyrotenax cable in this instance provided the following requirements be complied with:-


- (1) Current ratings, subject to voltage drop, to be no greater than those pertaining to paper insulated or varnished cambric insulated cables.
- (2) The installation to be carried out in the same way as with lead covered cable and subject to the same requirements, including bonding and earthing.

I have to add that the cable sizes given on the plan refer to stranded conductors, which are not used for Pyrotenax cables. In the circumstances, I shall be glad if you will arrange for a further amended plan to be forwarded, giving the actual areas of the conductors.

I am, Dear Sir,  
Yours faithfully,

The Secretary,  
GLASGOW.

W1163-0180



© 2020

Lloyd's Register  
Foundation