

Messrs. Bremer Vulkan's No. 757.

It is submitted the Bremen Surveyors be informed that the proposal made by the Owners to increase from 25 to 28 mm the diameter of the rivets in the quadruple riveted butts of the deck stringer plate where the same is increased in thickness at the ends of the bridge and at the forward end of the poop is concurred in.

It is assumed that the increased thickness of the deck stringer plate extends outside the forward end of the bridge as contemplated by the Rules and as shewn on the approved deck plan, and does not terminate inside the bridge as would appear from the rough diagrammatic sketch forwarded by them.

Dr. 14.6.38
Recd. 15.6.38
1 sketch returned
P.C. Adams

[Signature]
15. 6. 38.



© 2020

Lloyd's Register
Foundation

W1168-0026