

COPY.

ORDER NO. B. 39759.

6th November 1934.

Messrs. Superheater Co. Ltd.,
Bush House,
Aldwych,
LONDON. W. C. 2.

Job No. 109-1.
S.S. "HOBEETOR".

OUR SYMBOL NOS. 11B1, 11B2, and 11B3.


Superheaters "S" type suitable for 3 single ended forced draught boilers 15'0" x 11'9" long each having 3 furnaces coal fired and total heating surface of 7,500 sq. ft. To give a final temperature at the boilers of 610°F on 30,000 lbs. of steam per hour (total evaporation 34,000) with elements projecting 3" into combustion.

Accessories - 12 drain valves.
1 long distance thermometer with 25 ft. capillary tubing.
4 straight type thermometers.
1 soot lance with hose.
3 " cleaning valves.
Studs, bolts nuts &c.

To Lloyds Survey and to approved drawings.

Working pressure 200 lbs. per sq. inch.

Delivery - 3/4 week as quoted, or earlier.



© 2021

Lloyd's Register

Foundation