

WEST HARTLEPOOL

19th. November 1921.

David Mc.Auslan.

the Builders, Messrs Irvines Shipbuilding and Dry Docks Co. Ltd.
survey the steel screw steamer "CYNTHIANA" (Yard No. 587) No.
36725 in the Supplement of the Register Book, whilst the vessel
was lying afloat at the Builders Middleton Shipyard on the 2nd.
November 1921 and subsequently, for the purpose of ascertaining
the damage stated to have been sustained through the S.S.
"Tabarka" having collided with her on the 23rd. October 1921
whilst she lay at the Builders Slip fitting out.

On examination the damage sustained was found to
be as follows:-

(Shell plates and frames &c numbered from aft).

Found

Recommended

Port side:-

Shell &c the following plates
framing, &c buckled and indented.

Shell. No. 5 plate of M. strake

To be renewed.

buckled and indented.



© 2080
W1172-02772
Lloyd's Register
Foundation

Gross
Less C
Less a

No 4 plate of N strake indented.

To be cut off faired and
refitted.

No 3 plate of N strake and No 4
of L indented.

To be faired in place.

Frames:- (in shelter tween
decks) Nos. 26, 27 and 28 frames
buckled and set in.

To be cut out and renewed

No 29 frame and web plate in No
25 frame buckled and set in.

To be cut out faired and
refitted.

No 23 and 25 frames set in.

To be faired in place.

Shelter deck beams:-

Nos. 26, 27, 28 and 29 beams and
knees buckled.

To be removed faired and
refitted.

One deck plate in way of beams
buckled.

To be faired in place.

Starboard side:-

Shell:- No 7 plate of H strake
buckled and indented.

To be removed faired and
refitted.

One plate of J strake adjoining,
indented.

To be faired in place.

Frames:- One frame in way of shell
damage set in.


To be faired in place.

In addition to the foregoing, it was also recommended that all
removals which might be found necessary should be replaced in
good condition; that all new and repaired work should be recoated,
and that all the above mentioned repairs and work incidental
thereto should be completed in a satisfactory manner so as to
place the vessel in as good and efficient a condition as before
the damage was sustained.

Fee:- £3:3:0.

Surveyor to Lloyd's Register.

Paid 17/12/21. G.H.H.



© 2020

Lloyd's Register
Foundation

2/1710-2711M